SECTION 1

QFCI Jm

Date: 27/05/11

Exhibit Number:



TABLE OF CONTENTS

SECTION 1	Table of Contents, Controlled Copy Distribution List and Document Control Sheet
SECTION 2	Emergency Evaluation Procedures
SECTION 3	Notification & Emergency Communication List
SECTION 4	Introduction to EAP, Responsibilities & Dam Description
SECTION 5	Emergency Identification, Evaluation and Actions
SECTION 6	Scenario 2: Rapid Drawdown Scenario 3: Sunny Day Failure (Earthquake or Piping) Scenario 4: Chemical /Toxic Spill Scenario 5: Terrorist Activity Emergency Event Operation Recording Procedures Emergency Event Recording Sheets Flood Operation record sheet Sunny Day Failure (Earthquake) record sheet Sunny Day Failure (Piping) record sheet Chemical / Toxic Spill record sheet Terrorist Activity record sheet
SECTION 7	Emergency Access Routes & Preventative Actions • Preventative Actions • Alternative Access Routes • Locality Plan
SECTION 8	Lowering Storage Level and Spillway Gate Operations Lowering the Storage Level Spillway Gate – Routine and Emergency Operation Spillway Discharge Rating Curve
SECTION 9	Design Flood Estimation, Flood Impact Downstream & Inundation Maps
SECTION 10	 Definitions and Analysis Incident, Emergency Response, Crisis and Business Continuity Management Manual Flood Event Definitions and Abbreviations Earthquake Assessment (Modified Mercalli Scale)

Queensland Disaster Management System Weather Information (Flood Warning)



CONTROLLED COPY DISTRIBUTION

Copy Number	Position	Location
1	Storage Supervisor, Fairbaim Dam	SunWater – Fairbairn Dam
2	Service Manager/ EEC	SunWater – Emerald Depot
3	Area Operations Manager	SunWater - Area Operations Centre – North (Eton)
4	Manager, Asset Management	SunWater, Brisbane
5	Director, Dam Safety (Water Supply), Water Industry Compliance	DERM (Dept of Environment and Resource Management), Brisbane
6	Executive Officer – Local Disaster Management Group	Central Highlands Regional Council - Emerald
7	Coordinator – Disaster Management Local Disaster Management Group	Central Highlands Regional Council - Emerald
8	Duty Officer - Police	Police, Emerald
9	District Disaster Coordinator (Rockhampton)	Police, Rockhampton
10	Regional Director Emergency Management Queensland	Department of Community Safety, Rockhampton
11	Director Disaster Management Services, Emergency Management Queensland	State Disaster Coordination Centre - Department of Community Safety, Brisbane



DOCUMENT CONTROL SHEET

CONTROLLED COPY NUMBER:

4

AUTHORISATION:

Approved by:

Date:

November 2010

(Manager, Asset Management, Water Services)

ISSUE 2 of this EAP was prepared by Dam Safety Unit, Water Services, Brisbane.

REVISION STATUS:

JANUARY 2008
on Plan to

Note: Future updates to the Notification and Emergency Communication List (Section 3) as required by the Regulator (See Dam Safety Condition Schedule – Section 10) shall be compiled by the relevant SunWater Area Operations Centres and saved in HB File 08-000388/001. Once updating has been finalised the Area Operations Manager/Service Manager shall notify the Senior Engineer Headworks (SEH) – Brisbane, and the SEH will approve and organise the printing and distribution of this updated information to the 'Controlled Copy Holders' (see Section 3 for Phone numbers and addresses).

AMENDMENTS / SUGGESTIONS:

Description	Section	Suggestion Date
Principal Engineer, Dam Safety, Brisbane.		
Amendments to Sections 1, 2, 3, 5, and 10 Controlled Copy Sheet Update	1, P2	November '10
	Note: Any suggestion or comment should be forwarded to Principal Engineer, Dam Safety, Brisbane. Amendments to Sections 1, 2, 3, 5, and 10	Note: Any suggestion or comment should be forwarded to Principal Engineer, Dam Safety, Brisbane. Amendments to Sections 1, 2, 3, 5, and 10

SECTION 2



EMERGENCY EVALUATION PROCEDURES

Incident Level Description

Localised Incidents / Near Miss

ACTION 1 Will generally not escalate to an emergency

Incident managed by routine procedures and existing site resources.

Emergency

ACTION 2


May or may not result in activation of Crisis management Plan
Required a coordinated local response together with overview, advice

and action from subject matter expert in the Brisbane Office.

Crisis


ACTION 3 Critical / Catastrophic Consequences.


Significant diversion of management attention, time, energy and resources away from normal operation.




NOTES

- 1. All communication (advise) to be conducted in person, or via telephone.
- 2. The Procedure is intended to cover short term Emergency or Dam Safety Incident.
- 3. The Procedure is not intended for activation as a result/outcome of an extended analytical safety review of the dam.
- 4. Telephone numbers are available in the Notification & Emergency Communication List in Section 3.





SunWater Section 2: Page 4 of 5 Jan 08, Issue 2-0



SECTION 3



NOTIFICATION & EMERGENCY COMMUNICATION LIST

Telephone and Radio Notification List and Emergency Communication List

and

List of Equipment available during an Emergency

(# 593459 in HB File 08-000388/001)

AUTHORISATION:

Approved by:		Date:	
	Senior Engineer Headworks (SEH)		

AMENDMENT STATUS:

Amendment Number	Description	Amendment Date	
	Issue 2	June 2008	
2	Update Telephone & Radio Notification List	November 2009	
2A	Update Telephone & Radio Notification List	November 2010	



TELEPHONE & RADIO NOTIFICATION LIST

Central Office Management (Brisbane)						
TITLE/NAME	Phone Business	Phone Mobile	Phone A/H	Fax	Controlled Copy Holder Addresses	
Chief Executive Officer						
Manager, Asset Management 4						
rincipal Engineer Dam Safety						
Corporate Relations Manager						
fledia Advisor Glenn Pfluger)						
/Environmental Manage						
lood Operations Centre buty Engineer/Senior Ingineer						
enior Engineer eadworks	†					
Chief Civil Engineer						
	7					
Controlled EAP Copy F numbered (e.g. 2) and				ce (phone) with em	are expected, in the first ail only used to confirm	




Area Operations Centre – North (Eton) and Emerald Depot							
TITLE/NAME	Phone Business	Phone Mobile	Phone A/H	Fax	Controlled Copy Holder Addresses		
Area Operations Manager 3							
Service Manager Emerald 2							
Emergency Event Coordinator (EEC)							
Operations Supervisor- Emerald							
Civil Supervisor –Emerald							
Storage Operator – Fairbairn Dam 1							
Standby Storage Operator Fairbairn Dam							

Controlled EAP Copy Holders shown numbered (e.g. 2) and shaded grey

Note: All contacts required by the EAP are expected, in the first instance, to be by voice (phone) with email only used to confirm or provide additional details





SunWater Section 3: Page 4 of 10 Nov 09, Issue 2-1



	Department of Er	nvironment and Re	esource Manageme	ent (DERM)	
TITLE/NAME	Phone Business	Phone Mobile	Phone A/H	Fax	Controlled Copy Holder Addresses
Director Dam Safety (Water Supply) - DERM, (Peter Allen) 5					
Principal Engineer Dam Safety,(Ron Guppy)					
	Nation	al Security Hotli	ne –		16
		Stream Gaugin	g Stations		
Headwater (Storage)Level Recorder	No Phone Connection (Computer Link only)	-	-	-	SunWater Station-
Craigmore	No Phone Connection (Computer Link only)	-	140		SunWater Station-
Theresa Ck	No Phone Connection (Computer Link only)	-			SunWater Station-
				2-4	
		2 Way Ra	adio		
		•			

Controlled EAP Copy Holders shown numbered (e.g. 2) and shaded grey

Note: All contacts required by the EAP are expected, in the first instance, to be by voice (phone) with email only used to confirm or provide additional details



Affected Property Owners – Weemah Side								
TITLE/NAME	Phone Business	Mobile Phone	Home Phone	Fax	Address Lot/Plan			
		1						

Affected Property Owners – Selma Side								
TITLE/NAME	Phone Business	Mobile Phone	Home Phone	Fax	Address Lot/Plan			



ITILE/NAME Phone Business Mobile Phone Home Phone Fax Address Lot/Pl	FITI CINIA BAC	Dhone During	Makila Dirama	Harris Bli		A.1
	III LE/NAIVIE	Prione Business	Mobile Phone	Home Phone	Fax	Address Lot/Pla
			-	_		
			-	_		
						-30
						510
			-	-		
	_		-	_		
				_		
			-	_		
	-		-	_		
			-			_
			<u>.</u>			
						. 4
			_			
			-	_		
	-		-	-		-
	-		-	-		5
	-		-	_		
	_					
						1
						1
	-		-			
			-			



EMERGENCY CONTACTS

Please note: for a **chemical spill emergency** please phone (000) and ask for **Department of Community** Safety.

For general advice regarding chemical spills and hazardous waste please phone 31095099 (Dept of Community Safety)



PHONE: 000 for emergencies

Hazardous Industries & Chemicals Branch

For advice on large amounts of **chemicals stored**:

Chemical Hazards and Emergency Unit

http://www.deir.qld.gov.au/workplace/chem/index.htm

PHONE: 3109 0811

If you are not sure as to how to treat **POISONS** contact Queensland Health



13 11 26

http://www.health.qld.gov.au/PoisonsInformationCentre/default.htm

http://www.dcs.qld.gov.au

Department of Community Safety





The **State Disaster Management Group** is the principal organisation for disaster management throughout the State. This group is responsible for disaster mitigation and disaster planning and preparation at a state level and for conducting whole of Government response and recovery operations prior to, during and after a disaster impact. This includes accessing interstate and/or Commonwealth assistance when Local and State resources are exhausted or not available.

Emergency Management Queensland (EMQ), a division of the Department of Community Safety, provides the core policy and support staffing for the State Group. This includes the provision of disaster management training, management of the State Disaster Coordination centre, maintenance of the State Disaster Plan as well as training and equipment support to local volunteer SES units.

EMQ has regional staff across the State who assist Local Governments and State agencies in their counter disaster responsibilities.

PHONE: 3247 8943 (State Disaster Coordination Centre – 24 hr number)

Use of this number is to be restricted to emergency use only.

OR EMQ Regional Duty Officer (Central Region - |


State Duty Officer – Brisbane: PHONE:

Communications Branch

Level 5 Police Headquarters – 200 Roma St Brisbane 4000










LIST OF EQUIPMENT AVAILABLE DURING AN EMERGENCY



SECTION 4



INTRODUCTION TO EAP & RESPONSIBILITIES

4.0 INTRODUCTION

4.1 Purpose

This Plan defines responsibilities and procedures designed to identify conditions in time to take remedial action, including those which may endanger Fairbairn Dam, and to notify the appropriate authorities, Emergency Agencies and Public Officials of possible, impending, or actual failure of the dam. The location of the dam is provided in Section 7.

The main purpose of the Plan is to ensure that timely warning is provided to the appropriate Authorities and Emergency Agencies in the event of a major incident impacting on the dam, and to provide relevant information for use in the emergency response to the situation.

The Plan identifies emergency conditions at the dam, and describes procedures to be followed by SunWater staff to investigate those conditions and provide warning to appropriate authorities and emergency agencies in the event of a dam failure, so that they can implement measures for protection of the downstream communities and properties. The Plan also provides direction to operating staff for handling unsafe or emergency conditions, where dam failure is unlikely, so that the dam can be returned to a safe operating condition with minimal delay.

4.2 Classification Category

According to Queensland Dam Safety Management Guidelines 2002, Fairbairn Dam is classified with Category 2 Failure Impact Rating, having a population in excess of 100 people at risk.

4.3 Role of Emergency Event Coordinator (EEC)

Emergency Event Coordinator (EEC) is a role created in all SunWater Business Centres. The role will be activated during an emergency event (all hours) until the emergency is over. In the event of an emergency, the EEC will implement appropriate emergency procedures for which they have been trained.

Under normal operational conditions, the Asset Engineering Manager, Service Delivery Manager or Service Coordinator/Supervisor will perform this role. During an emergency condition any personnel trained for this role can serve as the Emergency Event Coordinator.



4.4 RESPONSIBILITIES

Organisation	Responsible Position / (s)	General Responsibilities	Emergency Responsibilities
	Regional Manager	 Overall responsibility for water supply in the Business Centre. 	➤ Liaison with SunWater Management
	Service Delivery Manager / Coordinator	 Dam Management and Supervision. Provide Training for EEC 	 Local Media Liaison in conjunction with Manager Public Affairs. Site management coordination.
SunWater Business	Emergency Event Coordinator (EEC)	See Section 4.3	Liaison with the internal management of SunWater.
Centre	Asset Engineering Manager (AEM)	 Delivering of Dam Safety Program in the Business Centre. Provide Training for EEC 	 Liaison with MAM and PEDS in Brisbane. Liaison with Emergency Event Coordinator. Activation of Emergency Response.
	Dam Duty Operator (DDO)	Dam Maintenance, Surveillance and Operation	 Identification & notification of unsafe condition. Implement preventive measures as directed by EEC or TSE.
	Manager, Asset Management (MAM)	 Overall responsibility for safe operation & maintenance of SunWater infrastructure in Queensland. 	 ➤ Advice SunWater Management ➤ Advise Dam Regulator ➤ Advice Manager, Public Affairs ➤ Liaison with Management & Regulator
Head Office	Principal Engineer, Dam Safety (PEDS)	 Formulation and implementation of Dam Safety Management Program & analysis of dam behaviour. 	 Advise Business Centres on Dam Safety Issues Warning for dam failure and protective measures. Analysis of information & recommendations
	Manager, Public Affairs	 Responsible for media relations, communications and public relations activities. 	 Liaison with Management Liaison with Regulator Liaison with Business Centre Liaison with media



4.4 RESPONSIBILITIES (Cont'd)

Organisation	Responsible Position / (s)	General Responsibilities	Emergency Responsibilities
Police	District Disaster Coordinator	Preparation of disaster plans and conduct of emergency operations.	 Co-ordinate & support to SunWater during a declared emergency at the dam.
Police	Local Police	Liaison with relevant organisations.	 Evacuation of persons, if required. Control of essential traffic. Security of specific area.
	Counter Disaster & Rescue Services	Liaises in the preparation of disaster plans and conduct emergency operations.	 Point of contact for State Government response to emergency situations.
	District Disaster Coordinator	Preparation of district disaster management plans and coordinates district response.	➤ To provide and coordinate whole-of- government support to disaster stricken communities
State Counter Disaster Organisation	Local Government Disaster Management Group	 Preparation of local disaster management plans and coordinates local response. Decide what resources are needed, when they are needed and how best to apply such resources so as to minimise hardship and suffering. 	 Provision and control of Council man-power and equipment as required. Provision of emergency accommodation.
	Counter Terrorism Liaison Officer	Identifies area of concern during the preparation of disaster plans.	
Dam Safety, NR&W	Director, Dam Safety	 Oversight of Dam Safety practice at all referable dams in Queensland 	Liaison with relevant Minister on necessary actions.



4.5 DAM DESCRIPTION SHEET

(Data obtained from Dam Safety Review, September 1999)

Main Dam

Type Central Clay Core with Outer Rockfill

Zones

Full Supply Level (FSL)¹ EL 204.23 m AHD

Storage Capacity at FSL 1,301,133 ML

Storage Area at FSL 15,000 ha

Embankment Crest Level 218.86 m AHD

Height of Dam above Foundation 46.33 m (approx)

Length Across Crest 823 m

Spillway

Spillway Crest Level EL 204.23 m AHD

Spillway Capacity at DCL 21,400 cumecs (through Spillway only)

Spillway Type Chute with Uncontrolled Ogee Crest

Crest Length 163.07 m,(excl. width of bridge piers)

Outlet Works

Number of Outlets 2 (on either Side of Abutment)

Saddle Dams

Number of Saddle Dams 6

Saddle Dams Type Homogeneous Earth Fill

¹All levels are to Australian Height Datum, AHD. Conversion for Fairbairn Dam is AHD=(State Datum in feet x 0.3048)-0.293) m

SECTION 5



EMERGENCY IDENTIFICATION, EVALUATION AND ACTIONS

The dam has been designed to conform to the latest accepted design standards, so that its failure is highly unlikely. In order to maintain the dam in a safe condition and detect any emergency conditions, as soon as it begins to develop, or becomes apparent, the following is applicable to Fairbairn Dam.

5.1 Inspections

The following inspections are conducted at Fairbairn Dam:

- Routine Visual Inspection
- Conducted Weekly
- Detailed Inspection
- Conducted Annually
- Comprehensive Inspection
- Conducted Five-yearly

5.2 Instrumentation and Monitoring

To confirm the structural behaviour and safety of the embankment the following Instrumentation was installed, and are monitored, at Fairbairn Dam.



The location of instrumentation and monitoring equipment are listed in Section 6C.

5.3 Emergency Identification

Five major possible emergencies have been identified at SunWater Dams, which are:



- Emergency Event due to extreme inflow floods overtopping the Dam.
- Emergency Event due to rapid drawdown of the reservoir.
- Emergency Event due to a rapidly deteriorating structural deficiency such as may be induced by an extreme earthquake or erosion of the foundations and abutments.
 (This is the so-called "Sunny Day" Failure, i.e. not induced by an inflow flood).
- Emergency Event due to a chemical/toxic spill.
- Emergency Event due to a terrorist activity (threat/hoax).

5.4 EVALUATION OF INCIDENTS

It is considered that **ACTION 1 – Localised Incident/Near Miss**, is to be locally contained, with a short-term impact (generally reported in the Monthly Dam Surveillance Report). Although each emergency condition will be evaluated and responded to individually, the action of most emergencies will be similar and follow procedures outlined below.

5.5.1 Flood Operation

All flood events, at or above Full Supply Level EL 204.23 m, will require the Dam Duty Operator to inform the Emergency Event Coordinator, who will further activate the following Emergency Evaluation Procedure

ACTION 2

5.4.2 Imminent Dam Failure

At Fairbairn Dam, if a staff member observes evidence of an imminent dam failure, such as water flowing through a breach in the dam, he/she will inform the Dam Duty Officer and/or Emergency Event Coordinator, who will activate the following Emergency Evaluation Procedure

ACTION 3

5.4.3 Unsafe or Unusual Conditions

If during a routine inspection, or at any other time, an unsafe or unusual condition is detected, the Fairbairn Dam staff will immediately notify the Dam Duty Officer and/or Service Delivery Coordinator, Emerald, who will advice the Principal Engineer (Dam Safety), and/or Manager (Asset Management), so that an evaluation of the situation can be carried out and a determination can be made on the condition of the dam.

If the Asset Engineering Manager, and/or Service Delivery Manager, following an inspection of the dam, and in consultation with Principal Engineer (Dam Safety), and/or Manager (Asset



Management), determine that potential for the failure of the dam exists then he/she will activate the following Emergency Evaluation Procedure

ACTION 3

If the unsafe or unusual condition will not lead to failure of the dam in the short term the Asset Engineering Manager, and/or Service Delivery Manager, will activate the following Emergency Evaluation Procedure

ACTION 2

Scenario 1: Flood Operation

Under normal conditions, the operation of the storage is controlled by the on site Dam Duty Operator on advice from the Service Delivery Coordinator.

During flood events, the dam will be continuously manned and will be controlled from the Regional Centre, Biloela. The Dam Duty Operator will keep the Emergency Event Coordinator informed of discharge through the spillway. The Emergency Event Coordinator will then inform the Asset Engineering Manager, who will further keep the Local Government Disaster Management Group (LGDMG) informed of the discharge through the spillway. In particular, the following alerts will be sent to the District Disaster Coordinator and Counter Disaster & Rescue Services in Brisbane.

The flood emergency event will start after the storage level has reached Full Supply Level (EL 204.23 m). In all other cases, follow the Operation and Maintenance Manual/s, and Standing Operating Procedures.

Water Level at Fairbairn Dam	AEP	Flood Alert Level Colour Code	Discharge volume (MLD)
Storage at Full Supply Level (EL 204.23 m and Rising)	•		
Storage above 204.23m and, approaching EL 206.67 m	(*)		Discharge 95,700 MLD
Storage above EL 206.67 m, approaching EL 207.4 m			Discharge = 147,000 MLD
Storage above EL 207.4 m, approaching EL 211 m	1:50		Discharge = 500,000 MLD
Storage above EL 211 m, approaching EL 217.83 m	PMF		Discharge = 1,496,448 MLD

		(s	ALL ACTION MUST BE TAKEN WHEN IT IS SAFE TO DO SO taking photographs/video, dam inspections, instrument reading	eering Duty
		Asset Engineering Manager (AEM)	Customer Council members of Nogoa Mackenzie water supply scheme Advice the Dam Duty Operator of any inflow flood information obtained from the Bureau of Meteorology (Section 10, Page 7) *www.bom.gov.au *www.bom.gov.au Notify as often as requested	Principal Engineer, Dam Safety IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
ario 1: Flood Operation [STAGE 1]	ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)	Record all communication Mogoa Mackenzie we network daily or as required and advise the Dam Duty Operator of upstream river flows Notify the Flood Warning Centre, Brisbane of rainfall at dam and the storage height daily or as required See note # below Table of Personnel to be notified Notify as often as requested Acustomer Council me Nogoa Mackenzie we scheme Advice the Dam Duty Operator of any inflow flood informobtaing to a required any inflow flood informobtaing to rainfall at dam and the Section 10, Page 7) See note # below Table of Personnel to be notified Notify as often as requested Asset Engineering Manager Coordinator Service Delivery Manager	Principal Engineer, Dam Safety IMPORTANT When the storage level peaks and beging the Local Governr Operator.
Scenario 1: Flood Ope	A	Dam Duty Operator (DDO)	Record all events and communication Monitor and record the rainfall - daily Monitor storage level - 12 hourly Log book entries as per SOP 12 & 22 See note # below Contact local Radio Stations 4HI and Table Radio Stations 4HI and Contact local Radio Stations 4HI and Table Emergency Event Coordinator Emergency Event Coordinator	# After the Event an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator and forward unedited copies to the Service Delivery Manager Biloela and the Manager, Asset Management, Brisbane
			FOR RECORD: Use Sheets from Section 6 and 6A	ncy Even perator ar et Manago
		Stages	STAGE 1 Storage level at EL 204.23 m and Rising Slowly (General heavy rainfall and/or storms over the catchment)	# After the Event an Emergency Event Report shall be Coordinator and Dam Duty Operator and forward unedi

SunWater Section 5A: Page 2 of 6 Jan 08, Issue 2-0

Scenario 1: Flood Operation [STAGE 2]	ACTION TO BE TAKEN BY	Asset Engineering Manager 으 으 (AEM)	Advise the Dam Duty Operator of any inflow flood information obtained from the Bureau of Meteorology. (Section 10, Page 7) *www.bom.gov.au Record all communication Inform spillway discharge to all personnel listed in the table below.	Notify as often as requested Counter Disaster Executive Officer, Emerald Shire Police - Emerald Shire	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
		oordinator	Record all communication Monitor catchment inflow advisory Advise the Dam Duty Operator of network daily or as required and Advise the Dam Duty Operator of upstream river flows. Advise the Dam Duty Operator of any inflow flood information obtained from the Bureau Meteorology. Notify the Flood Warning Centre, Section 10, Page 7) Brisbane of rainfall at dam and the storage height daily or as required Fax the sheet 'Flood Operation' to all personnel listed in the table below. See note # below. See note # below. Total of Borgers I Emerald River Bridge at Emerald Total of Borgers I Emerald Advise the Dam Duty Operator and information obtained from the Bureau Meteorology. Section 10, Page 7) *www.bom.gov.au *wwww.bom.gov.au *www.bom.gov.au *www.bom.gov.au *www.bom.gov.au	Notify as often as requested • Asset Engineering Manager • Regional Manager • Principal Engineer, Dam Safety	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Managem and Dam Duty Operator.
		Dam Duty Operator (DDO)	 Record all events and communication Monitor Fairbaim Dam Gauging Station - 12 hourly Photograph spillway at downstream face - regularly Monitor and record the rainfall - daily Monitor storage level - 12 hourly Plot Storage Level vs. Time graph - twice a day Log book entries as per SOP 12 & 22 See note # below At storage level EL 206.2m AHD, access problem	Notify as often as requested • Standby Officer • Emergency Event Coordinator	# After the Event an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator and forward unedited copies to the Service Delivery Manager Biloela and the Manager, Asset Management, Brisbane
			CORD: Use Sheets from Section 6 and 6A	FOR RE	ency Ever y Operatu ınager, As
		Stages	STAGE 2 Water Level is above EL 204.23 m and approaching EL 206.67 m Spillway Flow up to 95,700 MLD		

SunWater Section 5A: Page 3 of 6 Jan 08, Issue 2-0

			OPST BE TAKEN WHEN IT IS SAFE TO DO SO	Photograp		Group
		Asset Engineering Manager (AEM)	Advise the Dam Duty Operator of any inflow flood information obtained from the Bureau of Meteorology (Section 10, Page 7) *www.bom.gov.au Record all communication Inform spillway discharge to all personnel listed in the table below.	t, Camp Fairbairn Administration	Notify as often as requested Counter Disaster Executive Officer, Emerald Shire Police - Emerald Shire.	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
ration [STAGE 3]	ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)	 Record all communication Monitor catchment inflow advisory network 6 hourly and advise the Dam Duty Operator of upstream river flows Notify the Flood Warning Centre, Brisbane of rainfall at dam and the storage height daily or as required Fax the sheet 'Flood Operation' to all personnel listed in the table below See note # below 	sts, Lake Maraboon Holiday Village Management and others informed during the flood event Table of Personnel to be notified	 Notify as often as requested Asset Engineering Manager Regional Manager Service Delivery Manager Principal Engineer, Dam Safety 	IMPORTANT When the storage level peaks and beg Engineering Manager shall notify the and Dam Duty Operator.
Scenario 1: Flood Operation [STAGE 3]		Dam Duty Operator (DDO)	 Record all events and communication Monitor Fairbairn Dam Gauging Station - 12 hourly Monitor flow at Spillway, and storage level - 6 hourly on chart Photograph Spillway at downstream face regularly. Monitor and record the rainfall Inspect the Embankment and read Instrumentation, as per the 'Flood Operation' sheet, and fax to EEC Log book entries as per SOP 12 & 22 See note # below 	Keep Fairbairn Dam residents, Tourists, Lake Maraboon Holiday Village Management, Camp Fairbairn Administration and others informed during the flood event Table of Personnel to be notified	Notify as often as requested • Standby Officer • Emergency Event Coordinator	# After the Event an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duly Operator and forward unedited copies to the Service Delivery Manager Biloela and the Manager, Asset Management, Brisbane
			Use Sheets from Section 6 and 6A	ECORD:	ноя к	ncy Ever Operate nager, As
		Stages	STAGE 3 Water Level is above EL 206.67 m and approaching EL 207.4 m	147,000 MLD		# After the Event an Emergency Event Report shall be jointly co Coordinator and Dam Duty Operator and forward unedited Manager Biloela and the Manager, Asset Management, Brisbane

SunWater Section 5A: Page 4 of 6 Jan 08, Issue 2-0

		Stages	STAGE 4 Water Level is above EL 207.4 m and approaching EL 207.4 m Spillway Flow upto Sol, 000 MLD PRECORD STAGE 4 OSE EL 211 m Spillway Flow upto SOL OR Fairbai OSE Fairbai	# After the Event an Emergency Event Report shall be jointly compiled by Coordinator and Dam Duty Operator and forward unedited copies to Manager Biloela and the Manager. Asset Management. Brisbane
Scenario 1: Flood Operation [STAGE 4]		Dam Duty Operator (DDO)	ents and commulat Spillway - 4 horesteed # 5 at downstreed record the rainfared main embankmoin readings notics as per SOP elow roadings as often as Standby O Emergency Event	# After the Event an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator and forward unedited copies to the Service Delivery Manager Biloela and the Manager. Asset Management. Brisbane
	ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)	Brecord all communication Monitor catchment inflow advisory network 4 hourly and advisory network 4 hourly and advisor the Dam Duty Operator of upstream river flows Monitor catchment inflow advisory network 4 hourly and advisor the Dam Duty Operator of upstream river flows Notify the Flood Warning Centre, Section 10, Page 7) Record all communication required errors per the storage height daily or as required errors below below to all personnel listed in the table personnel listed in the table below below See note # below ts. Tourists, Lake Maraboon Holiday Village Management, Camp Fairbairn Administration and others informed during the flood event Table of Personnel to be notified Notify as often as requested event Emerald Shire Socional Solvice Delivery Manager Police - Emerald Shire Police - Emerald Sh	IMPORTANT When the storage level peaks and beg Engineering Manager shall notify the and Dam Duty Operator.
		Asset Engineering Manager (AEM)	Advise the Dam Duty Operator of any inflow flood information obtained from the Bureau of Meteorology (Section 10, Page 7) *www.bom.gov.au Record all communication Inform spillway discharge to all personnel listed in the table below Camp Fairbairn Administration and Notify as often as requested Camp Fairbairn Administration and Emerald Shire Police - Emerald Shire.	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
		•	ALL ACTION MUST BE TAKEN WHEN IT IS SAFE TO DO SO	<u>e</u>

Section 5A: Page 5 of 6 Jan 08, Issue 2-0 SunWater

				CTION N	ALL A	Asset Group	
			Asset Engineering Manager (AEM)	 Advise the Dam Duty Operator of any inflow flood information obtained from the Bureau of Meteorology. (Section 10, Page 7) *www.bom.gov.au Record all communication Inform all personnel listed below of the spillway discharge when the depth of water passing through the spillway exceeds 1.5m, 3m and 4.5m, or as often as requested 	nts, Tourists, Lake Maraboon Holiday Village Management, Camp Fairbairn Administration and others informed during the flood event Table of Personnel to be notified	Notify as often as requested Counter Disaster Executive Officer, Emerald Shire Police - Emerald Shire.	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
ration [STAGE 5]	ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)	 Record all communication Monitor catchment inflow advisory network 4 hourly and advise the Dam Duty Operator of upstream river flows Notify the Flood Warning Centre, Brisbane of rainfall at dam and the storage height daily or as required Fax the sheet 'Flood Operation' to all personnel listed in the table below See note # below 	ake Maraboon Holiday Village Management, others informed during the flood event Table of Personnel to be notified	Notify as often as requested Asset Engineering Manager Regional Manager Service Delivery Manager	 IMPORTANT When the storage level peaks and Engineering Manager shall notify th and Dam Duty Operator. 	
Scenario 1: Flood Operation [STAGE 5]	AC	Dam Duty Operator (DDO)	 Record all events and communication Monitor flow at Spillway - 4 hourly, or as required Photograph Spillway, Tailwater at downstream face, and Saddle Dams - regularly Monitor and record the rainfall - 6 hourly Record storage level on Storage vs Time graph - hourly, or as required Inspect the dam regularly (hourly if reservoir level is within 0.5 m of the crests), as per the 'Flood Operation' sheet, and fax to EEC Immediately report any damage observed Log book entries as per SOP 12 & 22 See note # below 	Keep Fairbairn Dam residents, Tourists, Lake Mara others inf Table	Notify as often as requested • Standby Officer • Emergency Event Coordinator	# After the Event an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator and forward unedited copies to the Service Delivery Manager Biloela and the Manager. Asset Management. Brisbane	
			Use Sheets from Section 6 and 6A	ECORD:	FOR R	ency Eve ty Operat inager. As	
		Stages	STAGE 5 Water Level is above EL 211 m and approaching EL 217.83 m Spillway Flow upto	1,496,448 MLD		# After the Event an Emergency Event Report shall be jointly co Coordinator and Dam Duty Operator and forward unedited Manager Biloela and the Manager. Asset Management. Brisbane	

SunWater Section 5A: Page 6 of 6 Jan 08, Issue 2-0

EMER CANCY ACTION PLAN - FAIRBAIRN DAM

Scenario 3A: 'Sunny Day' Failure, due to Earthquake

(Event due to a rapidly deteriorating structural deficiency such as may be induced by an extreme earthquake)

	(sf	TO DO SO ment reading	IT IS SAFE ions, instru	qsm inspect	MUST BE T/	ALL ACTION king photogr	, et .g.9)	dnc
	Asset Engineering Manager (AEM)	Arrange an inspection of the dam and assess its condition	Notify as often as required Principal Engineer (Dam Safety) Manager (Asset Management)	 If unstable condition is established, advise the Dam Duty Operator to lower reservoir level. 	Notify as often as requested • Executive Officer, Local Disaster Management Group, Emerald Shire.	 Implement ACTION 3. (Page 2, Section 2) 	Notify as often as required • All personnel listed in ACTION 3. (Page 2, Section 2)	• IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group and Dam Duty Operator.
ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)		Notify as often as required Asset Engineering Manager	 If unstable condition is established, Implement ACTION 2. (Page 3, Section 2) 	Notify as often as required	 Implement ACTION 3. (Section 2, page 2) See note # below. 	 Notify as often as required All personnel listed in ACTION 3. (Page 2, Section 2) 	 IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Managem and Dam Duty Operator.
AC	Dam Duty Operator (DDO)	 Inspect the Embankment, Spillway Structure, and Abutments, forward report to EEC Check for springs, deformation, erosion, and concrete damage 	Notify as often as requested Standby Officer Emergency Event Coordinator	 Immediately inspect the Embankment, Spillway Structure, and Abutments, forward report to EEC Repeat the inspection every 12 hours 	Notify as often as requested • Standby Officer • Emergency Event Coordinator	 Lower reservoir level Photograph the damage from a safe point Vacate the immediate vicinity of the dam Forward event report to EEC (see note # below) 	Notify as often as required Standby Officer Emergency Event Coordinator	# After the Event, an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Dufy Operator, and unedited copies to be forwarded to the Service Delivery Manager Biloela and Manager (Asset Management), Brisbane.
		7 PC	ction 6 and	ets from Se	: Use She	ОК ВЕСОВО	ЭŦ	gency Eve y Operati nd Manag
	Stages	STAGE 1 Earthquake experienced in the area	Intensity less than 5 MM (refer to Section 10 for Modified Mercalli Scale)	STAGE 2 Earthquake experienced in the area	Intensity greater than 5 MM (refer to Section 10 for Modified Mercalli Scale)	STAGE 3 Dam Failure is imminent due to	Earthquake	# After the Event, an Emery Coordinator and Dam Dul Delivery Manager Biloela ar

SunWater Section 5C: Page 1 of 1 Jan 08, Issue 2-0

EMEK_ENCY ACTION PLAN - FAIRBAIRN DAM

Scenario 3B: 'Sunny Day' Failure, due to Piping

ALL ACTION MUST BE TAKEN WHEN IT IS SAFE TO DO SO Management Group, Emerald Shire Executive Officer, Local Disaster Arrange an inspection of the dam Principal Engineer (Dam Safety) advise the Dam Duty Operator to If piping condition is established, All personnel listed in ACTION 3 (Page 2, Section 2) Notify as often as requested Asset Engineering Manager Notify as often as required Notify as often as required When the storage level peaks and begins to fall at a constant rate, the Asset and assess its condition. Implement ACTION 3 ower reservoir level (Event due to a rapidly deteriorating structural deficiency such as may be induced by piping through the embankment, foundation or abutments) (YEM) (Page 2, Section 2) Principal Engineer (Dam Safety) If piping condition is established, Asset Engineering Manager All personnel listed in ACTION 3 **Emergency Event Coordinator** Notify as often as required Notify as often as required Notify as often as required observed initiate ACTION 2 If rapidly increasing trend is Implement ACTION 2 Implement ACTION 3 **ACTION TO BE TAKEN BY** (EEC) See note # below. Page 3, Section 2) (Page 2, Section 2) Page 2, Section 2) (Page 3, Section 2) IMPORTANT Monitor flows until a decreasing trend is observable, Monitor flows until a decreasing trend is observable, Vacate the immediate vicinity of the embankment # After the Event, an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator, and unedited copies to be forwarded to the Service Photograph the seepage and piping from a safe Forward event report to EEC (see note # below) Notify as often as requested Notify as often as requested Notify as often as required **Emergency Event Coordinator** Emergency Event Coordinator Emergency Event Coordinator Dam Duty Operator or as directed by the EEC or as directed by the EEC (00d) Standby Officer Standby Officer Standby Officer Lower reservoir level. **FOR RECORD:** Use Sheets from Section 6 and 6D imminent due to Piping Large Increasing Flows Water Level at Full Supply Increasing Leakage **Embankment with** Stages Dam Failure is (FSL 204.23 m) **Embankment** cloudy water through the through the STAGE 2 STAGE 3 STAGE 1 Level

(e.g. taking photographs/video, dam inspections, instrument readings)

SunWater Section 5D: Page 1 of 1 Jan 08, Issue 2-0

Engineering Manager shall notify the Local Government Disaster Management Group

and Dam Duty Operator.

Delivery Manager Biloela and Manager (Asset Management), Brisbane.

	Manager	0.0000	equired es Manager ssment on Department in ous Algal 9, Section 10)	ealth	NOITOA JIA		the Asset
	Asset Engineering Manager (AEM)		Notify as often as required • Environmental Services Manager Who will then make an assessment on whether to notify the Health Department in accordance with the Hazardous Algal Bloom Response plan (Page 9, Section 10)	s its water quality for water s ital Services Manager, and t	ards and Emergency Unit aster Co-ordinator		MPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset Engineering Manager shall notify the Local Government Disaster Management Group
ACTION TO BE TAKEN BY	Emergency Event Coordinator (EEC)		Notify as often as required Asset Engineering Manager	 Inspect the reservoir and assess its water quality for water supply Coordinate with the Environmental Services Manager, and the Health Department 	Notify immediately Response Unit of the State Government Chemical Hazards and Emergency Unit if it is a very large spill then also notify the District Disaster Co-ordinator	Notify as often as requested Emergency Event Coordinator	IMPORTANT When the storage level peaks and begins to fall at a constant rate, the Asset
A	Dam Duty Operator (DDO)	* Sketch, measure, photograph and locate its position in the reservoir/catchment * Forward event report to EEC	Notify as often as required Emergency Event Coordinator	 Sketch, measure, photograph and locate its position in the reservoir/catchment Close all outlet structures Forward event report to EEC (see note # below) 	 Mobile Spill Response Unit of the and if it is a very large s 	No •	# After the Event, an Emergency Event Report shall be jointly compiled by the Emergency Event Coordinator and Dam Duty Operator, and unedited copies to be forwarded to the Service Delivery Manager, and Manager (Asset Management), Brisbane.
		39	from Section 6 and	D: Use Sheets	ОК КЕСОК	d	Event R
	Stages	STAGE 1	Large amount or Chemical / Toxic Spill found in the reservoir/catchment Use Page 1, Section 6E	STAGE 2 Large amount of	Chemical / Toxic Spill found in the reservoir/catchment Use Page 1, Section 6E		# After the Event, an Emergency

SunWater Section 5E: Page 1 of 1 Jan 08, Issue 2-0

SECTION 6



EMERGENCY EVENT OPERATION RECORDING PROCEDURES

- Emergency Event Recording Sheets
 - Emergency Event Record ** (Page 3, this Section)
 - Record of Communication ** (Page 4, this Section)
 - Log of Events / Actions ** (Page 5, this Section)
- ** Note: These sheets must be completed for all Emergency Event Scenarios, and included in the Emergency Event Report.
- Operating Procedure
 - o Flood Operation (See Section 6A)
- Operating Procedure
 - Rapid Drawdown (Not applicable at Fairbairn Dam)
- Operating Procedure
 - Sunny Day Failure (Earthquake) (See Section 6C)
 - Sunny Day Failure (Excessive Seepage → Piping) (See Section 6D)
- Operating Procedure
 - Chemical / Toxic Spill (See Section 6E)
- Operating Procedure
 - Terrorist Activity (See Section 6F)



Emergency Event Recording Sheets

- Emergency Event Record
- Record of Communication sheet
 - Log of Events / Action sheet

Note: These sheets must be completed for all Emergency Event Scenarios and be included in the Emergency Event Report

EMERGENCY ACTION PLAN - FAIRBAIRN DAM

EMERGENCY EVENT RECORD

COMPLETE THIS COVER SHEET AND ATTACH RELEVANT RECORDING SHEETS FROM SECTION 6.

	Spillway discharge	Earthquake P	iping Water Quality	Terrorist Activity	
mencina:	Time: am/pm; [Date / ./	Finishing: Time	: am/pm; Date/	
2. DESC	RIPTION OF THE EVEN	l			
h relevant	sheets from Section 6.				
3. STATI	STICS				
	Total inflow			Megalitres	
	Total discharge			Megalitres	
	Capacity of Storage pri	or to inflow		%	
	Volume prior to inflow			Megalitres	
	Maximum inflow			MLD	
	Maximum discharge			MLD	
	f the Spillway Level vers a Flood Event. (Section		Record of Communication,	the Log of Events / Actions,	an
fall during of the fall during of the fall during of the fall during the fall during the fall during of the	a Flood Event. (Section RAL COMMENTS	6A)		the Log of Events / Actions, red Reporting, Safety issues, or any su	
5. GENE nclude in this sentich may impro	A Flood Event. (Section RAL COMMENTS Exction any observations or commented to the Event AGE REPORT	6A) Ints regarding the Event, suc		red Reporting, Safety issues, or any su	

ENLIRGENCY ACTION PLAN - FAIRBAIRN DAM

FAIRBAIRN DAM - EMERGENCY ACTION PLAN RECORD OF COMMUNICATION

RECORDED BY (INITIALS)							
MESSAGE							
CALL IN / OUT							
CONTACT PERSON / TELEPHONE NO.							
TIME							
DATE							

SunWater Section 6: Page 4 of 5 Jan 08, Issue 2-0

ELL.RGENCY ACTION PLAN - FAIRBAIRN DAM

FAIRBAIRN DAM EMERGENCY ACTION PLAN LOG OF EVENTS / ACTIONS

Date	Time	Event description / Action carried out	Recorded By (initials)

SunWater Section 6: Page 5 of 5 Jan 08, Issue 2-0

Flood Operation

Visual Inspection and Storage Report Note: See Page 5 for instructions **

Page 1 of 4

VISU	AL INSPECTION		First Inspection	Second Inspection (+6 hrs)	Third Inspection (+12 hrs)
		DATE			
		TIME			
	Valk OR Drive at 10 km/hour. Write 'W' for w	/alk and 'D' to	r Drive)		
Main Dam Embankment					
	General	Condition			
	Cracks, subsidence in	pavement			
Upstream Face (Use binoculars):	S	ettlement			
	Displacement of ripra	p material			
Downstream face:	Subsidence, slides	, erosion			
	Sign of seepage, Wet spot	s / seams			
Area Downstream of Dam					
Seepac	e from any location apart from seep	page point			
Seepage	, , , , , , , , , , , , , , , , , , , ,	<u> </u>			
	Seepage water - Clear or Turbid	(Tick for clear)			
Spillway	Seepage water - Olear or Turbia	(Tick for cical)			
Spillway Channel	Erosion, damage to concrete	structure	ĺ.		
	General Condition/Cracking				
Trainings Walls:	General Condition/Oracking				
U/S Face (if visible):					
Apron (if visible):	General Condition / Impac				
Crest (if visible):	General C				4
	Impac	t Damage			4
Bridge: General Co	ondition/Cracking/Spalling/Construc	tion Joints			
Details of significant changes. New	occurrences and issues warranting further	attention			*

					,
	Inspecting Office				
	Fax to	Asset En Manager		nager / Servic	e Delivery
	(tick if faxed)	Principal	Engineer (Da	m Safety)	

Flood Operation

Visual Inspection and Storage Report Note: See Page 5 for instructions ** Page 2 of 4

VISUAL INSPECTION		First Inspection	Second Inspection (+6 hrs)	Third Inspection (+12 hrs)	
	DATE				
	TIME				
(Walk OR Drive at 10 km/hour. Write 'W' for w	alk and 'D' for	Drive)			
River					
Left Bank: General Condition/Seepage/Slip	s/Slumps				
Seepage/Erosion	/Deposits				
Right Bank: General Condition/Seepage/Slip	s/Slumps				
Intake Structure					
Structure: General Condition/Cracking/Spalling/Impact	Damage				
Trashracks/Baulks: General Condition/Coatins/Impact	Damage				
Access Bridge: General Condition/Cracking/Spalling/Impac	Damage				
Outlet Works Right Bank					
Outlets: General Condition/Cavitation/Cracking	g/Spalling				
Channel: General Condition/Loose Rock/Erosion	/Deposits				
Culverts: General Condition/Cracking/Spalling/S	ettlement				
Bull Ring: General Condition/Cracking/Spalling/Dama	ge/Joints				
Outlet Works Left Bank (if Accessable)					
Outlets: General Condition/Cavitation/Crackin	g/Spalling				
Channel: General Condition/Loose Rock/Erosion.	/Deposits				
Culverts: General Condition/Cracking/Spalling/S	ettlement				
Pump House: General Condition/Cracking/	/Damage				
Selma Channel Gate House: General Condition/Cracking	/Damage				
Details of significant changes. New occurrences and issues warranting further	attention				
Inspecting Office	er's initials				
Fax to	Asset En- Manager	gineering Ma	nager / Servic	e Delivery	
(tick if faxed)	Principal	l Engineer (Dam Safety)			

Flood Operation

Visual Inspection and Storage Report Note: See Page 5 for instructions ** Page 3 of 4

VISUAL INSPECTION		First Inspection	Second Inspection (+6 hrs)	Third Inspection (+12 hrs)	
	DATE				
	TIME				
(Walk OR Drive at 10 km/hour. Write 'W' for walk	and 'D' for	Drive)			
Saddle Dam Embankments (Earth & Rockfill Structure)			ii.		
Saddle Dam 1					
Crest: Depressions/Cracks/Sinkholes/Alignment/E	rosion				
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressions/B	Erosion				
Drainage 9	System				
U/S Slope: Slides/Sinkholes/Beaching/E	rosion				
Left Abutment: Cracks/Wetspots	/Slides				
Right Abutment: Cracks/Wetspots	/Slides				
Saddle Dam 2					
Crest: Depressions/Cracks/Sinkholes/Alignment/E	Erosion				
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressions/B	Erosion				
Drainage :	System				
U/S Slope: Slides/Sinkholes/Beaching/E	Frosion				
Left Abutment: Cracks/Wetspots	/Slides				
Right Abutment: Cracks/Wetspots	/Slides				
Saddle Dam 3					
Crest: Depressions/Cracks/Sinkholes/Alignment/E	Erosion				
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressions/B	Erosion				
Drainage	System				
U/S Slope: Slides/Sinkholes/Beaching/E	Erosion				
Left Abutment: Cracks/Wetspots	eft Abutment: Cracks/Wetspots/Slides				
Right Abutment: Cracks/Wetspots	s/Slides				
Details of significant changes. New occurrences and issues warranting further atte	ention				
Inspecting Officer's					
Fax to	Asset Eng Manager		nager / Service	Delivery	
(tick if faxed)	Principal	Engineer (Dam Safety)			

Flood Operation

Visual Inspection and Storage Report Note: See Page 5 for instructions ** Page 4 of 4

	VISUAL INSPECTION		First Inspection	Second Inspection (+6 hrs)	Third Inspection (+12 hrs)	
		DATE				
		TIME				
0.10.0.5.5.	(Walk OR Drive at 10 km/hour. Write 'W' for	valk and 'D' fo	r Drive)			
	kments (Earth & Rockfill Structure)					
Saddle Dam 4						
Crest:	Depressions/Cracks/Sinkholes/Alignme	nt/Erosion				
D/S Slope: Cracks/Si	inkholes/Bulging/Wetspots/Boils/Depression	ns/Erosion				
	Draina	ge System				
U/S Slope:	Slides/Sinkholes/Beachin	g/Erosion				
Left Abutment:	Cracks/Wetsp	ots/Slides	-			
Right Abutment:	Cracks/Wetsp	ots/Slides				
Saddle Dam 5						
Crest:	Depressions/Cracks/Sinkholes/Alignme	nt/Erosion				
D/S Slope: Cracks/Si	inkholes/Bulging/Wetspots/Boils/Depression	ns/Erosion				
		ge System				
U/S Slope:	Slides/Sinkholes/Beachin		-			
Left Abutment:	Cracks/Wetsp					
	Cracks/Wetsp					
Right Abutment:	Cracks/vvetsp	Ols/Sildes				
Saddle Dam 6						
Crest:	Depressions/Cracks/Sinkholes/Alignme					
D/S Slope: Cracks/Si	inkholes/Bulging/Wetspots/Boils/Depression	ns/Erosion				
	Draina	ge System				
U/S Slope:	Slides/Sinkholes/Beachin	g/Erosion				
Left Abutment:	Cracks/Wetsp	ots/Slides				
Right Abutment:	Abutment: Cracks/Wetspots/Slides					
Details of significant chan	ges. New occurrences and issues warranting further	attention				
	Inspecting Offic	er's initials				
	Fax to	Asset Eng Manager		nager / Service	Delivery	
	(tick if faxed)	Principal	Engineer (Dai	m Safety)		

** INSTRUCTION FOR COMPLETING SHEET - Flood Operation

STAGE 1

- Monitor Fairbairn Dam Gauging Station 12-hourly
- Plot Rainfall vs. Storage Level daily

STAGE 2

- Monitor Fairbairn Dam Gauging Station 12 hourly
- Plot Storage Level vs. Time graph twice a day.

STAGE 3

- Inspect the Embankment and read Instrumentation, as per the 'Flood Operation' sheet
- Monitor Fairbairn Dam Gauging Station 12 hourly

STAGE 4

- Inspect the Embankment and read Instrumentation regularly
- Monitor Fairbairn Dam Gauging Station 6 hourly

STAGE 5

- Inspect the Embankment and read Instrumentation regularly
- Monitor Fairbairn Dam Gauging Station 6 hourly

VISUAL INSPECTION

Frequency of visual inspection required is indicated by

STAGE 3 ONCE A DAY STAGE 4 TWICE A DAY

STAGE 5 THREE TIMES A DAY

Additional Inspections should be made

When specifically requested

Show results of inspections as follow:-

New Seepage point.
 Seepage from any location apart from seepage points

NEW

• Significant increase (> 30%) or change in condition.

SG-INC

• Slight increase (> 10%) or change in condition.

INC

NIL change of condition.

NIL

• Slight decrease (< 10%) or change in condition.

DEC

Significant Changes

Any changes which, in the opinion of the inspecting officer, are more than just slight changes must be advised to Principal Engineer (Dam Safety), Brisbane. The degree of urgency of this advice varies with the nature of the matter.

TABLE 1 RECORD OF RAINFALL AND WATER LEVEL DURING FLOOD EVENT

Date	Time	Rainfall mm	Daily Total	Comments
			*	
		-		

FAIRBAIRN DAM HYDRAULIC PIEZOMETER READINGS

(Required if storage level is higher than EL 207 M and safe to do so)


				s higher th			t to do 80	4.
- 8	First In:	spection	Second I	nspection	Third In	spection	Fourth Ir	spection
Tip No	Inlet	Outlet	Inlet	Outlet	Inlet	Outlet	Inlet	Outlet
1								
2								
3								
4								
5								
6								
7								
8								
9								
10		-						
11 12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22								1
23								
24								
25						1		
26								
27								
28								
29								
30								
31	-							
32 33								k
34		1		1				
35								
36								
37								
38								
39								
40								
41								
42								
43								
44								
45								
46								

Fairbairn Dam Instrumentation Readings (Required if storage level is higher than EL 207 M and safe to do so)

ELECTRIC PIEZOMETERS

Piezometer	1 ST Inspection	2 ND Inspection	3 RD Inspection	4 [™] Inspection
EP01				8
EP02			Đ	#1
EP03				
EP04				
EP05			-	=
EP06				
EP07				
EP08				
EP09				*
EP10				
EP11				
EP12				
EP13				
EP14				
EP15				

STORAGE LEVEL AT SPILLWAY VERSUS TIME



Sunny Day Failure (Earthquake)

Visual Inspection and Storage Report

Page 1 of 4

	INSPECTION	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
	DATE				
	TIME				
	Storage Water Level EL (m) (FSL 204.23)				
	Daily Rainfall (mm) (Walk OR Drive at 10 km/hour. Write 'W' for	r walk and 'D' fo	r Drive)		
Main Dam Embankment					
	Gener	al Condition			
	Cracks, subsidence	in pavement			
Upstream Face (Use binocula	rs):	Settlement		1 =	
	Displacement of rip	rap material			
Downstream face:	Subsidence, slid				
	Sign of seepage, Wet sp	oots / seams			
Area Downstream of Dan					
	page from any location apart from se	epage point			
Seepage					
	Seepage water - Clear or Turb	oid (Tick for clear)			
Spillway					
Spillway Channel	Erosion, damage to concre				
Trainings Walls:	General Condition/Crack				
U/S Face :	Gener	al Condition			
Apron :	General Condition / Impa				
Crest :		al Condition			
		act Damage			
	Condition/Cracking/Spalling/Constru				
Details of significant changes. N	ew occurrences and issues warranting furth				
	Inspecting Of	ficer's initials			
	Fax to	Asset Er Manage		nager / Servic	e Delivery
	(tick if faxed)	Principal	Engineer (Da	am Safety)	

Sunny Day Failure (Earthquake)

Visual Inspection and Storage Report Note: See Page 5 for instructions ** Page 2 of 4

1.00	CHAL INCRECTION	Earthquake experienced	First Inspection	Second Inspection	Third Inspection
VISUAL INSPECTION Earthquake Intensity experienced:		ехрепенсец	Inspection	(within 12 hrs)	(+12 hrs)
Lartifquake inter	DATE			121115)	
	TIME				
	Storage Water Level EL (m) (FSL 204.23)				
	Daily Rainfall (mm)				
	(Walk OR Drive at 10 km/hour. Write 'W' fo	r walk and 'D' fo	r Drive)		
River					
Left Bank:	General Condition/Seepage/S	Slips/Slumps			
	Seepage/Erosi	on/Deposits			
Right Bank:	General Condition/Seepage/S	lips/Slumps			
Intake Structure					
Structure:	General Condition/Cracking/Spalling/Impa	act Damage			
Trashracks/Baulks	: General Condition/Coatins/Impa	act Damage			
Access Bridge:	General Condition/Cracking/Spalling/Impa	act Damage			
Outlet Works Right	t Bank				
Outlets:	General Condition/Cavitation/Crack	ing/Spalling			
Channel:	General Condition/Loose Rock/Erosi	on/Deposits			
Culverts:	General Condition/Cracking/Spalling	/Settlement			
Bull Ring:	General Condition/Cracking/Spalling/Dar	mage/Joints			
Outlet Works Left I	Bank				
Outlets:	General Condition/Cavitation/Crack	ing/Spalling			
Channel:	General Condition/Loose Rock/Erosic	on/Deposits			
Culverts:	General Condition/Cracking/Spalling	/Settlement			
Pump House:	General Condition/Crackir	ng/Damage			
Selma Channel Ga	te House: General Condition/Cracki	ng/Damage			
	nges. New occurrences and issues warranting furth				
	Inspecting Off	icer's initials			
	Fax to	Asset Engi Manager	neering Mana	ger / Service [Delivery
	(tick if faxed)	Principal E	ngineer (Dam	Safety)	

Sunny Day Failure (Earthquake)

Visual Inspection and Storage Report
Note: See Page 5 for instructions **

Page 3 of 4

Note: See Page 5 for instructions **				
VISUAL INSPECTION Earthquake Intensity experienced:MM	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
DATE				
TIME				
Storage Water Level EL (m) (FSL 204.23)				
Daily Rainfall (mm)				
(Walk OR Drive at 10 km/hour. Write 'W' fo	r walk and 'D' f	or Drive)		
Saddle Dam Embankments (Earth & Rockfill Structure)				
Saddle Dam 1				
Crest: Depressions/Cracks/Sinkholes/Alignm				
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi				
	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wets	spots/Slides			
Saddle Dam 2				
Crest: Depressions/Cracks/Sinkholes/Alignm	Depressions/Cracks/Sinkholes/Alignment/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wet	spots/Slides			
Saddle Dam 3				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wet	spots/Slides			
Details of significant changes. New occurrences and issues warranting furth				
Inspecting Off				
Fax to	Asset E Manage		nager / Servic	e Delivery
(tick if faxed)	Principa	l Engineer (Da	am Safety)	

Sunny Day Failure (Earthquake)

Visual Inspection and Storage Report

Page 4 of 4

	Earthquake	First	Second	Third
VISUAL INSPECTION Earthquake Intensity experienced:	experienced	Inspection	Inspection (within	Inspectior (+12 hrs)
Earthquake Intensity experienced:MM DATE			12 hrs)	
TIME				
Storage Water Level EL (m)				
(FSL 204.23)				
Daily Rainfall (mm)	. II I IDI 6-	Div		
(Walk OR Drive at 10 km/hour. Write 'W' for	walk and 'D' to	r Drive)		
Saddle Dam Embankments (Earth & Rockfill Structure)				
Saddle Dam 4				
Crest: Depressions/Cracks/Sinkholes/Alignme	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression	ns/Erosion			
Draina	age System			
U/S Slope: Slides/Sinkholes/Beachi	ng/Erosion			
Left Abutment: Cracks/Wets	pots/Slides			
Right Abutment: Cracks/Wets	pots/Slides			
Saddle Dam 5				
Crest: Depressions/Cracks/Sinkholes/Alignme	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression				
	age System			
U/S Slope: Slides/Sinkholes/Beachi				
Left Abutment: Cracks/Wets	_			
	pots/Sildes			
Saddle Dam 6				
Crest: Depressions/Cracks/Sinkholes/Alignme				
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression	ns/Erosion			
Draina	age System			
U/S Slope: Slides/Sinkholes/Beachi	ng/Erosion			
Left Abutment: Cracks/Wets	pots/Slides			
Right Abutment: Cracks/Wets	pots/Slides			
Details of significant changes. New occurrences and issues warranting furthe	r attention		l.	
Inspecting Office	cer's initials			
spounig oin		l gineering Mar	l nager / Service	Delivery
Fax to	Manager			
(tick if faxed)	Principal	Engineer (Da	m Safety)	

** INSTRUCTIONS FOR COMPLETING SHEET - Sunny Day Failure (Earthquake)

VISUAL INSPECTION

Frequency of visual inspection required is indicated by

Earthquake Less than 5mm COMPLETE FIRST VISUAL INSPECTION ONLY Earthquake greater than 5mm COMPLETE ALL VISUAL INSPECTIONS AND INSTRUMENTATION DATA AS WELL

Additional Inspections should be made, when:

- New seepage which requires further action
- · When specifically requested

Show results of inspections as follow:-

• New Seepage appeared.

NEW

• Significant increase (> 30%) or change in condition.

SG-INC

• Slight increase (> 10%) or change in condition.

INC

• NIL change of condition.

NIL


Slight decrease (< 10%) or change in condition.

DEC

Significant Changes

Any changes which, in the opinion of the inspecting officer, are more than just slight changes must be advised to the Principal Engineer (Dam Safety), Brisbane. The degree of urgency of this advice varies with the nature of the issue.





Instrumentation Readings

(REQUIRED IF EARTHQUAKE GREATER THAN 5 MM) SURFACE SETTLEMENT POINTS							
0.41	SURFACE	SEITLEIV	IENI POINI	3			
Settlement Point	1 ST Inspection	2 ND Inspection	3 RD Inspection	4 [™] Inspection			
CS1							
CS2							
CS3							
CS4							
CS5	V		ž .	l le			
CS6							
SS1							
SS2							
SS4							
SS5							
SS6							
SS7							
SS8		,					
SS9							
SS10							
SS11							
SS12							
SS13							
SS14							
SS15							
SS16							
SS17							
SS18							
SS19							
SS20							
SS21							
SS22							
SS23							
SS24							
SS25				2			
SS26							
SS27							
SS28							
	ELECTRIC	CSETTLEN	MENT POIN	rs			
ES A							
ES B							
ES C			я				
ES D							
ES E							
ES F							

SEEPAGE MEASUREMENT (REQUIRED IF EARTHQUAKE IS GREATER THAN 5MM)								
	мY	First Inspection	Second Inspection	Third Inspection	Fourth Inspection			
SR01	mm		et.	a a	v			
SR02	mm							
SR03 (Seepage point D/S	mm S of Bull Ring)							

	(REQUIRED IF EARTHQUAKE IS GREATER THAN 5MM)							
	First Ins	spection		nspection		spection		spection
p	Inlet	Outlet	Inlet	Outlet	Inlet	Outlet	Inlet	Outlet
1								
2								
3								
4								
5								
6						V		=1
7								
9								
10								
11								
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22 23								
24								
25								
26								
27								
28								
29								
30								
31								
32								
33								
34								
35								
36								
37								
38 39								
40								
41								
42								
43								
44								
45								
46								

Instrumentation Readings (REQUIRED IF EARTHQUAKE GREATER THAN 5 MM)

ELECTRIC PIEZOMETERS

Piezometer	1 ST Inspection	2 ND Inspection	3 RD Inspection	4 [™] Inspection
EP01				
EP02				
EP03				
EP04				
EP05				
EP06				
EP07				
EP08				
EP09			a	
EP10				
EP11				
EP12				
EP13				
EP14				
EP15			-	

Sunny Day Failure (Piping)

Visual Inspection and Storage Report Note: See Page 5 for instructions **

Page 1 of 4

VISUAL INSPECTION	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
DATE				
TIME				
Storage Water Level EL (m) (FSL 204.23)				
Daily Rainfall (mm)		- D-i)		
(Walk OR Drive at 10 km/hour. Write 'W' for Main Dam Embankment	or walk and 'D' to	r Drive)		
Gener	ral Condition			
Cracks, subsidence	in pavement			
Upstream Face (Use binoculars):	Settlement			
Displacement of rip	orap material		- 4	
Downstream face: Subsidence, slid	es, erosion			
Sign of seepage, Wet sp	oots / seams			
Area Downstream of Dam				
Seepage from any location apart from se	epage point			
Seepage				
Seepage water - Clear or Turb	oid (Tick for clear)			
Spillway				
Spillway Channel Erosion, damage to concre	ete structure			
Trainings Walls: General Condition/Crack	ing/Spalling			
U/S Face : Gener	al Condition			
Apron : General Condition / Impa	act Damage			
Crest: Gener	al Condition			
Imp	act Damage			
Bridge: General Condition/Cracking/Spalling/Constru	uction Joints			
Details of significant changes. New occurrences and issues warranting furth	er attention			
Inspecting Off				
Inspecting Off Fax to (tick if faxed)		gineering Man	nager / Service	Delivery

Sunny Day Failure (Piping)

Visual Inspection and Storage Report Note: See Page 5 for instructions **

Page 2 of 4

V	ISUAL INSPECTION	•	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
	DA	_				
	TIN Storage Water Level EL (
	(FSL 204.	23)				
	Daily Rainfall (m (Walk OR Drive at 10 km/hour. Write 'V		ralk and 'D' fo	(Drivo)		
River	(VVAIK ON DIIVE At 10 KIII/III0II. VVIILE V	V 101 V	vaik and D 10	Dilve)		
Left Bank:	General Condition/Seepag	e/Slip	s/Slumps			
	Seepage/E	osior	/Deposits			
Right Bank:	General Condition/Seepag	e/Slip	s/Slumps			
Intake Structure						
Structure:	General Condition/Cracking/Spalling/Ir	npact	Damage			
Trashracks/Baulks	s: General Condition/Coatins/Ir	npact	Damage			
Access Bridge:	General Condition/Cracking/Spalling/I	mpac	t Damage			
Outlet Works Righ	ıt Bank					
Outlets:	General Condition/Cavitation/Cr	ackin	g/Spalling			
Channel:	General Condition/Loose Rock/E	osior	/Deposits			
Culverts:	General Condition/Cracking/Spal	ing/S	ettlement			
Bull Ring:	General Condition/Cracking/Spalling/	Dama	ge/Joints			
Outlet Works Left	Bank					
Outlets:	General Condition/Cavitation/Cr	ackin	g/Spalling			
Channel:	General Condition/Loose Rock/Er	osion.	/Deposits			
Culverts:	General Condition/Cracking/Spal	ing/S	ettlement			
Pump House:	General Condition/Cra	cking/	Damage			
Selma Channel Ga	ate House: General Condition/Cra	cking	/Damage			
Details of significant ch	anges. New occurrences and issues warranting f	urther	attention			
	Inspecting	Office	er's initials			
	Fax to (tick if faxed)		Manager		ger / Service [Delivery
	(tick ii raxeu)		Principal Er	ngineer (Dam	Safety)	

Sunny Day Failure (Piping)

Visual Inspection and Storage Report Note: See Page 5 for instructions **

Page 3 of 4

VISUAL INSPECTION	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
DATE				
TIME				
Storage Water Level EL (m) (FSL 204.23)				
Daily Rainfall (mm)				
(Walk OR Drive at 10 km/hour. Write 'W' fo	or walk and 'D' fo	r Drive)		
Saddle Dam Embankments (Earth & Rockfill Structure)				
Saddle Dam 1				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wets	spots/Slides			
Saddle Dam 2				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ning/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wet	spots/Slides			
Saddle Dam 3				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depressi	ions/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ning/Erosion			
Left Abutment: Cracks/Wets	spots/Slides			
Right Abutment: Cracks/Wet	spots/Slides			
Details of significant changes. New occurrences and issues warranting furth				
L C - Of				
Inspecting Off		ginocring Mar	nager / Service	Dolivery
Fax to	Managei		iagei / Service	a Delively
(tick if faxed)	Principal	Engineer (Da	m Safety)	

Sunny Day Failure (Piping)

Visual Inspection and Storage Report Note: See Page 5 for instructions **

Page 4 of 4

VISUAL INSPECTION	Earthquake experienced	First Inspection	Second Inspection (within 12 hrs)	Third Inspection (+12 hrs)
DATE				
TIME				
Storage Water Level EL (m) (FSL 204.23)	4			1
Daily Rainfall (mm)				1
(Walk OR Drive at 10 km/hour. Write 'W' fo	r walk and 'D' fo	r Drive)		
Saddle Dam Embankments (Earth & Rockfill Structure)				
Saddle Dam 4				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	pots/Slides			
Right Abutment: Cracks/Wets	spots/Slides			
Saddle Dam 5				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	pots/Slides			
Right Abutment: Cracks/Wets	spots/Slides			
Saddle Dam 6				
Crest: Depressions/Cracks/Sinkholes/Alignm	ent/Erosion			
D/S Slope: Cracks/Sinkholes/Bulging/Wetspots/Boils/Depression	ons/Erosion			
Drain	age System			
U/S Slope: Slides/Sinkholes/Beach	ing/Erosion			
Left Abutment: Cracks/Wets	pots/Slides			
Right Abutment: Cracks/Wets	spots/Slides			
Details of significant changes. New occurrences and issues warranting further	er attention			
Inorposting Off	icar's initials			
Inspecting Offi Fax to	Asset Eng	gineering Man	ager / Service	Delivery
(tick if faxed)	Manager Principal	Engineer (Dar	n Safety)	

** INSTRUCTIONS FOR COMPLETING SHEET - Sunny Day Failure (Piping)

VISUAL INSPECTION

Frequency of visual inspection required is indicated by

STAGE 1 ONCE A DAY STAGE 2 TWICE A DAY STAGE 3 AS DIRECTED

Additional Inspections should be made, when:

- New seepage which requires further action
- When specifically requested

Show results of inspections as follow:-

• New Seepage appeared.

NEW

• Significant increase (> 30%) or change in condition.

SG-INC

• Slight increase (> 10%) or change in condition.

INC

NIL change of condition.

NIL

• Slight decrease (< 10%) or change in condition.

DEC

Significant Changes

Any changes which, in the opinion of the inspecting officer, are more than just slight changes must be advised to the Principal Engineer (Dam Safety), Brisbane. The degree of urgency of this advice varies with the nature of the issue.



Visual Inspection and Storage Report Note: Refer to Page 2 for recording instructions ** SUN	TUE	WED	THU First Inspection	Date:	SAT
Stored Water Level FSL 204.23m Outlet discharge MLD Oaily Rainfall (mm) VISUAL INSPECTION Reservoir	TUE		First	Second	SAT
Stored Water Level FSL 204.23m Outlet discharge MLD Oaily Rainfall (mm) VISUAL INSPECTION Reservoir		Pot			
Oaily Rainfall (mm) VISUAL INSPECTION Reservoir	8	Peter			
Oaily Rainfall (mm) VISUAL INSPECTION Reservoir		D.A.			
VISUAL INSPECTION Reservoir		Data			
		Data			Third Inspection (+48hrs)
		Date			
		Time			
escription of the Chemical/Toxic Spill Approx dista	ance from da	am wali			
ocation of Spill in the Reservoir/Catchment		OR DEF		TION AS AN AN	
Chemical Spill Management (tick if action		OR DEF		TION AS AN AN	ITD DISTAN TIME
tick if action Outlet structures closed (tick if action		OR DEF			
Chemical Spill Management (tick if action		OR DEF			

Inspecting Officer's initials

Fax to (tick if faxed)

SunWater Section 6E: Page 1 of 2 Jan 08, Issue 2-0

Asset Engineering Manager / Service Delivery

Principal Engineer (Dam Safety)

Manager

** INSTRUCTIONS FOR COMPLETING SHEET - Chemical/Toxic Spill

VISUAL INSPECTION	
Frequency of visual inspection required is indicated by ONCE A DA	Υ
Additional Inspections should be made, when	
When specifically requested	
Show results of inspections as follow:-	
New Seepage appeared	NEW
• Significant increase (> 30%) or change in condition.	SG-INC
Slight increase (> 10%) or change in condition.	INC
NIL change of condition.	NIL
 Slight decrease (< 10%) or change in condition. 	DEC


Significant Changes

Any changes which, in the opinion of the inspecting officer, are more than just slight changes must be advised to the Principal Engineer (Dam Safety). The degree of urgency of this advice varies with the nature of the issue.





SunWater Section 6E: Page 2 of 2 Jan 08, Issue 2-0











SECTION 7



EMERGENCY ACCESS ROUTES & PREVENTIVE ACTIONS

7. EMERGENCY ACCESS ROUTES

Locality plan and alternative access routes are shown on Page 2 of this Section.


7.1 PREVENTIVE ACTIONS

In the event of a rapidly deteriorating structural deficiency which is likely to threaten the security of the dam (for example, due to internal erosion or following a major earthquake), the Dam Duty Operator or Standby Officer, having reported a potential emergency situation, should follow the preventive actions set out below:-

- 1. Ensure that a responsible person with portable communication is left in a safe position at the dam to monitor the emergency condition.
- 2. Restrict access to the dam area.
- 3. Liaise with Service Delivery Manager and Asset Engineering Manager who will liaise with Emergency Management Authorities.
- 4. If possible, document the emergency condition with photographs and or video camera.
- 5. Update Service Delivery Manager and Asset Engineering Manager from time to time of any change in the emergency condition.
- 6. Do not take any unnecessary risks in undertaking the above actions.

Since the most likely scenarios for a dam failure at Fairbairn Dam is from 'Sunny Day' Failure, the stability may be increased by using available earth and rock fill material as a stabilising berm. A list of equipment (earthmoving), available during an emergency, is provided in Section 3.

It may become necessary during an emergency to lower the reservoir level of the dam to decrease seepage and/or loading on the structure, and to minimise the impact of any failure. This would only be an option where an emergency condition was identified in the early stages. Instructions for operation of the outlet works are given in Section 2.6 of the Operation and Maintenance Manual for the dam.



SECTION 8



LOWERING STORAGE LEVEL

8.0 LOWERING THE STORAGE LEVEL

It may become necessary during an emergency to lower the Fairbairn Dam storage level to decrease seepage and/or loading on the structure to minimise the impact of any failure. This would only be an option when an emergency condition has been identified in its early stages. Instructions for operation of the Outlet Works are provided in Section 2.6 of the Operation & Maintenance Manual for the dam.

8.1 Fairbairn Dam Constraints

There are three constraints that need to be considered when evaluating lowering of the storage level. These are:


- 1. Maximum possible releases from Fairbairn Dam; and,
- 2. Flooding Impacts Downstream.
- 3. Availability of Left Bank Outlet Works during flood


8.1.1 Maximum possible releases from Fairbairn Dam


The release rate from the storage may be governed by the storage level at the time of drawdown. The possible mechanisms, which can be operated is through the outlets


Dewatering Options	Inflow	Number of Days required to Lower the Reservoir level
ТВА	Without Inflow	To EL m - Days
ТВА	With Inflow	


Outlet works curves for rapid drawdown are shown on Page 2











SECTION 9



DESIGN FLOOD ESTIMATION

The PMP estimate for the 96 hour storm event produced a peak storage level of EL 218.59m AHD which would overtop the crest elevation of saddle dams 1, 5 and 6 (EL 217.94m AHD) by 0.65 metres. Peak inflows, outflows, flood volumes and peak storage levels were calculated for the 96 hour storm duration and range of AEP's. Table 9.1 summarises the peak flood estimates for the critical storm duration.

Table 9.1: Fairbairn Dam - Peak flood estimates - 96 hour critical storm duration

AEP (1 in Y)	PMP Depth (mm)	Estimated Peak Inflow m³/s	Estimated Peak Outflow m ³ /s	Flood Volume ML	Peak Storage Level (m AHD)
50	245	966	587	478 000	205.87
100	275	1742	1183	848 000	206.78
200	306	3685	2760	1 740 000	208.47
500	346	4764	3666	2 260 000	209.27
1000	377	5628	4393	2 670 000	209.87
2000	409	6541	5166	3 100 000	210.46
5000	473	8461	6811	4 030 000	211.61
10 000	558	11095	9018	5 300 000	213.04
50 000	979	24768	23452	12 000 000	218.36
61 275 (PMF)	1070	27777	26969	13 500 000	218.59

FLOOD IMPACTS DOWNSTREAM

Tables below show the summarised information of the Dam Break Study conducted by SunWater in 2003.

The peak flood level results are presented as plots of extent of inundation. Figures 9.1 to 9.3 show plots of the longitudinal profiles of the peak flood levels along the Nogoa-Mackenzie Rivers.

Tables 9.1 to 9.3 summarise the peak flood levels at key locations.



Table9.1: Sunny Day Failure Flood Levels

Stream Location		Peak Flood Level (m, AHD)
Nogoa	1. Fairbairn Dam Tailwater	199.2
Nogoa	2. Selma Weir	193.8
Nogoa	3. Emerald – Capricorn Hwy	193.2
Nogoa	4. Emerald Town Weir	190.1
Nogoa	5. Bellmah	183.4
Nogoa	6. McCoskers Weir	180.6
Nogoa	7. Retreat Ck Junction	174.5
Nogoa	8. Bridge Flats Crossing	171.4
Nogoa	9. Crinum Ck Junction	163.7
Nogoa	10. Wyuna	162.6
Nogoa	11. Duckponds Homestead	158.1
Nogoa	12. Currimundi	155.2
Nogoa Right	13. Lochlees	165.6
Nogoa Right	14. Parker Developments	171.4
Nogoa Right	15. Braylands	165.6
Mackenzie	16. St Aubins	153.5
Mackenzie	17. Rileys Crossing	152.1
Mackenzie	18. Yackam	149.3
Mackenzie	19. Carnangarra	147.5
Comet	20. Myrtle Park	153.5
Comet	21. Comet Town Weir	153.5
Comet	22. Comet – Capricorn Hwy	153.5
Theresa	23. Kingower Billabong	175.4
Theresa	24. Blair Athol Railway Line	174.4
Retreat	25. Trafalgar	175.0
Retreat	26. Blair Athol Railway Line	174.5
Retreat	27. Gregory Highway	174.7
Retreat Right	28. Washpool Waterhole	174.7
Retreat Left	29. Codenwarra Pump Site	174.7
Gordonstone	30. Langley Downs	163.7
Crinum	31. Belong Ck Junction	163.7



Crinum	32. Wyuna Road	163.7
Crinum	33. Colorada	163.7
Mosquito	34. Fenceline	163.7
Winton	35. Locharbor	167.0
Winton	36. Bauhinias Road	159.6
Winton	37. Duckponds Lagoon	157.1
Boggy	38. Ensham	155.4
Sandhurst	39. Karvella	153.5
Sandhurst	40. Capricorn Hwy	153.5

Table 9.2: Probable Maximum Flood - No Failure Flood Levels

Stream	Location	Peak Flood Level (m, AHD)
Nogoa	Fairbairn Dam Tailwater	197.7
Nogoa	2. Selma Weir	189.4
Nogoa	3. Emerald – Capricorn Hwy	183.8
Nogoa	4. Emerald Town Weir	178.9
Nogoa	5. Bellmah	175.8
Nogoa	6. McCoskers Weir	174.8
Nogoa	7. Retreat Ck Junction	174.4
Nogoa	8. Bridge Flats Crossing	172.0
Nogoa	9. Crinum Ck Junction	165.0
Nogoa	10. Wyuna	164.2
Nogoa	11. Duckponds Homestead	160.4
Nogoa	12. Currimundi	159.0
Nogoa Right	13. Lochlees	163.6
Nogoa Right	14. Parker Developments	172.1
Nogoa Right	15. Braylands	160.8
Mackenzie	16. St Aubins	158.6
Mackenzie	17. Rileys Crossing	157.6
Mackenzie	18. Yackam	153.5
Mackenzie	19. Carnangarra	149.4
Comet	20. Myrtle Park	158.8



Comet	21. Comet Town Weir	158.7
Comet	22. Comet – Capricorn Hwy	158.6
Theresa	23. Kingower Billabong	180.8
Theresa	24. Blair Athol Railway Line	177.6
Retreat	25. Trafalgar	178.1
Retreat	26. Blair Athol Railway Line	176.2
Retreat	27. Gregory Highway	175.7
Retreat Right	28. Washpool Waterhole	175.4
Retreat Left	29. Codenwarra Pump Site	175.5
Gordonstone	30. Langley Downs	165.1
Crinum	31. Belong Ck Junction	165.7
Crinum	32. Wyuna Road	165.1
Crinum	33. Colorada	165.0
Mosquito	34. Fenceline	165.1
Winton	35. Locharbor	167.1
Winton	36. Bauhinias Road	160.7
Winton	37. Duckponds Lagoon	160.1
Boggy	38. Ensham	159.0
Sandhurst	39. Karvella	158.6
Sandhurst	40. Capricorn Hwy	158.6

Table 9.3: Probable Maximum Flood - Dam Failure Flood Levels

Stream	Location	Peak Flood Level (m, AHD)
Nogoa	1. Fairbairn Dam Tailwater	204.9
Nogoa	2. Selma Weir	202.7
Nogoa	3. Emerald – Capricorn Hwy	201.7
Nogoa	4. Emerald Town Weir	193.8
Nogoa	5. Bellmah	188.4
Nogoa	6. McCoskers Weir	187.7
Nogoa	7. Retreat Ck Junction	187.2
Nogoa	8. Bridge Flats Crossing	183.3
Nogoa	9. Crinum Ck Junction	169.5



	T to w	100.4
Nogoa	10. Wyuna	169.1
Nogoa	11. Duckponds Homestead	167.9
Nogoa	12. Currimundi	166.2
Nogoa Right	13. Lochlees	172.8
Nogoa Right	14. Parker Developments	181.9
Nogoa Right	15. Braylands	168.5
Mackenzie	16. St Aubins	165.7
Mackenzie	17. Rileys Crossing	164.3
Mackenzie	18. Yackam	158.6
Mackenzie	19. Carnangarra	150.2
Comet	20. Myrtle Park	165.7
Comet	21. Comet Town Weir	165.7
Comet	22. Comet – Capricorn Hwy	165.7
Theresa	23. Kingower Billabong	188.4
Theresa	24. Blair Athol Railway Line	188.4
Retreat	25. Trafalgar	188.4
Retreat	26. Blair Athol Railway Line	188.4
Retreat	27. Gregory Highway	188.4
Retreat Right	28. Washpool Waterhole	188.4
Retreat Left	29. Codenwarra Pump Site	188.5
Gordonstone	30. Langley Downs	169.5
Crinum	31. Belong Ck Junction	169.5
Crinum	32. Wyuna Road	169.5
' Crinum	33. Colorada	169.5
Mosquito	34. Fenceline	169.5
Winton	35. Locharbor	168.0
Winton	36. Bauhinias Road	168.0
Winton	37. Duckponds Lagoon	168.0
Boggy	38. Ensham	166.2
Sandhurst	39. Karvella	165.7
Sandhurst	40. Capricorn Hwy	165.7




Figure 9.1: Sunny Day Failure - Peak Levels

SunWater Section 9: Page 6 of 15 Jan 08, Issue 2-0




Figure 9.2: PMF No Failure - Peak Levels

SunWater Section 9: Page 7 of 15 Jan 08, Issue 2-0

Figure 9.3: PMF with Failure - Peak LevelsTime to Peak Flood Levels

SunWater Section 9: Page 8 of 15 Jan 08, Issue 2-0



The time of start of rise and time to peak for various key locations is summarised in Tables 9.4 to 9.6 for the scenarios simulated. This summary provides an indication of the available response time for each of the sites indicated.

The times shown are measured from the start of the event. For the Sunny Day Failure, the start of the event coincides with the start of the formation of the breach, which begins forming at the dam crest. For the probable maximum flood events, the times are measured from the start of the rainfall event.

Table 9.4: Sunny Day Failure Flood Rise Times

Stream	Location	Time to Start of Rise (dd:hh:mm)	Time to Peak Flood Level (dd:hh:mm)
Nogoa	1. Fairbairn Dam Tailwater	0:00:00	0:07:00
Nogoa	2. Selma Weir	0:02:20	0:07:20
Nogoa	3. Emerald – Capricorn Hwy	0:02:20	0:07:40
Nogoa	4. Emerald Town Weir	0:03:00	0:08:00
Nogoa	5. Bellmah	0:03:40	0:10:40
Nogoa	6. McCoskers Weir	0:04:20	0:11:00
Nogoa	7. Retreat Ck Junction	0:04:40	0:11:20
Nogoa	8. Bridge Flats Crossing	0:05:40	0:12:00
Nogoa	9. Crinum Ck Junction	0:06:40	0:13:40
Nogoa	10. Wyuna	0:07:00	0:18:40
Nogoa	11. Duckponds Homestead	0:09:20	0:23:40
Nogoa	12. Currimundi	0:10:20	1:01:40
Mackenzie	16. St Aubins	0:12:00	1:11:20
Mackenzie	17. Rileys Crossing	0:13:20	1:18:20
Mackenzie	18. Yackam	0:16:00	1:19:20
Mackenzie	19. Carnangarra	0:17:20	1:20:20



Table 9.5: Probable Maximum Flood - No Failure Rise Times

Stream	Location	Time to Start of Rise (dd:hh:mm)	Time to Peak Flood Level (dd:hh:mm)
Nogoa	Fairbairn Dam Tailwater	0:00:00	6:19:00
Nogoa	2. Selma Weir	0:06:40	6:20:40
Nogoa	3. Emerald – Capricorn Hwy	0:08:00	6:22:40
Nogoa	4. Emerald Town Weir	0:08:40	6:23:00
Nogoa	5. Bellmah	0:12:20	7:14:00
Nogoa	6. McCoskers Weir	0:14:20	7:16:20
Nogoa	7. Retreat Ck Junction	0:16:00	7:17:00
Nogoa	8. Bridge Flats Crossing	0:18:00	7:18:00
Nogoa	9. Crinum Ck Junction	0:22:00	7:19:20
Nogoa	10. Wyuna	0:22:20	7:20:20
Nogoa	11. Duckponds Homestead	1:02:20	8:09:40
Nogoa	12. Currimundi	1:07:00	8:14:00
Mackenzie	16. St Aubins	1:09:20	8:13:20
Mackenzie	17. Rileys Crossing	1:16:00	8:16:00
Mackenzie	18. Yackam	1:20:40	8:16:00
Mackenzie	19. Carnangarra	1:21:00	8:16:40

Table 9.6: Probable Maximum Flood - Dam Failure Rise Times

Stream	Location	Time to Start of Rise (dd:hh:mm)	Time to Peak Flood Level (dd:hh:mm)
Nogoa	Fairbairn Dam Tailwater	0:00:00	7:00:20
Nogoa	2. Selma Weir	0:06:40	7:01:20
Nogoa	3. Emerald – Capricorn Hwy	0:08:00	7:01:40
Nogoa	4. Emerald Town Weir	0:08:40	7:02:20
Nogoa	5. Bellmah	0:12:20	7:05:40
Nogoa	6. McCoskers Weir	0:14:40	7:06:20
Nogoa	7. Retreat Ck Junction	0:16:00	7:06:40
Nogoa	8. Bridge Flats Crossing	0:18:00	7:07:00
Nogoa	9. Crinum Ck Junction	0:22:00	7:15:20



Nogoa	10. Wyuna	0:22:20	7:16:20
Nogoa	11. Duckponds Homestead	1:02:20	7:18:40
Nogoa	12. Currimundi	1:07:00	7:22:40
Mackenzie	16. St Aubins	1:09:20	8:00:20
Mackenzie	17. Rileys Crossing	1:16:00	8:01:00
Mackenzie	18. Yackam	1:20:40	8:01:40
Mackenzie	19. Carnangarra	1:21:00	8:02:20

For the Sunny Day Failure Flood, the water level at the Capricorn Highway at Emerald (key location No.3) begins to rise approximately 2 hours after the start of the formation of the breach at the dam and peaks approximately 5½ hours later.

During a PMF flood with no dam failure, the water level at the Capricorn Highway at Emerald (key location No.3) begins to rise 8 hours into the storm event and peaks approximately 6 days 15 hours later.

For the PMF flood with dam failure, the water level at the Capricorn Highway at Emerald (key location No.3) begins to rise 8 hours into the storm event and peaks approximately 6 days 18 hours later. This is approximately 9 hours after the start of the formation of the breach at the dam which occurs 6 days 17 hours into the storm event.

For the two failure cases it is unlikely that there would be sufficient warning time to evacuate the population at risk. For the no failure case, evacuation may be possible.



Peak Flood Flows

Tables 9.7 to 9.9 summarise the peak flood flows at key locations.

Table 9.7: Sunny Day Failure Peak Flows

Stream	Location	Peak Flow (m³/s)
Nogoa	1. Fairbairn Dam Tailwater	98 500
Nogoa	2. Selma Weir	79 640
Nogoa	3. Emerald – Capricorn Hwy	70 800
Nogoa	4. Emerald Town Weir	60 540
Nogoa	5. Bellmah	42 370
Nogoa	6. McCoskers Weir	36 270
Nogoa	7. Retreat Ck Junction	14 400
Nogoa	8. Bridge Flats Crossing	16 640
Nogoa	9. Crinum Ck Junction	4 190
Nogoa	10. Wyuna	4 740
Nogoa	11. Duckponds Homestead	4 640
Nogoa	12. Currimundi	10 140
Mackenzie	16. St Aubins	12 030
Mackenzie	17. Rileys Crossing	5 320
Mackenzie	18. Yackam	8 110
Mackenzie	19. Carnangarra	8 640

Table 9.8: Probable Maximum Flood - No Failure Peak Flows

Stream	Location	Peak Flow (m³/s)
Nogoa	1. Fairbairn Dam Tailwater	16 735
Nogoa	2. Selma Weir	16 840
Nogoa	3. Emerald – Capricorn Hwy	16 830
Nogoa	4. Emerald Town Weir	16 830
Nogoa	5. Bellmah	10 610
Nogoa	6. McCoskers Weir	6 700
Nogoa	7. Retreat Ck Junction	10 260
Nogoa	8. Bridge Flats Crossing	16 360
Nogoa	9. Crinum Ck Junction	4 970
Nogoa	10. Wyuna	5 200

SunWater Section 9: Page 12 of 14

Jan 08, Issue 2-0



Nogoa	11. Duckponds Homestead	4 480
Nogoa	12. Currimundi	14 250
Mackenzie	16. St Aubins	21 710
Mackenzie	17. Rileys Crossing	6 520
Mackenzie	18. Yackam	13 850
Mackenzie	19. Carnangarra	21 640

Table 9.9: Probable Maximum Flood - Dam Failure Peak Flows

Stream	Location	Peak Flow (m³/s)
Nogoa	1. Fairbairn Dam Tailwater	225 350
Nogoa	2. Selma Weir	167 700
Nogoa	3. Emerald – Capricorn Hwy	156 010
Nogoa	4. Emerald Town Weir	155 000
Nogoa	5. Bellmah	55 360
Nogoa	6. McCoskers Weir	28 290
Nogoa	7. Retreat Ck Junction	35 300
Nogoa	8. Bridge Flats Crossing	44 010
Nogoa	9. Crinum Ck Junction	8 670
Nogoa	10. Wyuna	8 130
Nogoa	11. Duckponds Homestead	13 540
Nogoa	12. Currimundi	35 760
Mackenzie	16. St Aubins	44 810
Mackenzie	17. Rileys Crossing	11 770
Mackenzie	18. Yackam	21 980
Mackenzie	19. Carnangarra	43 510



On the basis of the current design flood revision carried out for Fairbairn Dam, it is concluded that:

- The duration of the critical PMF event reduces to 96 hours compared with the 120 hour duration found in the 1994 study,
- The 96 hour PMF peak storage level shall increase by 0.76m to EL 218.59m AHD compared with the 120 hour PMF peak storage level (EL 217.83m AHD) estimated in the 1994 study,
- The 96 hour PMF peak storage level shall overtop the crest levels of saddle dams 1, 5 and 6 (EL 217.94m AHD) by 0.65m and 0.27m below the crest levels of the main embankment and saddle dams 2, 3 and 4 (EL 218.86m AHD).

HYDROLOGICAL MODEL FLOODING IMPACTS STUDY SUMMARY

- The Sunny Day Failure Flood causes a similar extent of flooding to the PMF no failure flood. However, the Sunny Day Flood causes worse effects upstream close to the dam due the flood occurring more abruptly and with a higher peak. The PMF with failure causes by far the largest area of flooding over the whole area.
- The Capricorn Highway Road Bridge at Emerald would be inundated by 16.4m, 7.0m and 24.9m for the Sunny Day Failure, PMF with no failure, and PMF with failure events respectively. The Capricorn Highway Road Bridge at Comet would be inundated by 2.5m, 7.6m, and 14.7m for the same respective events. The Gregory Highway Road Bridge at Retreat Ck would be inundated by 1.6m, 2.6m, and 15.3m again, for the same respective events.
- For the Sunny Day Failure Flood, the water level at the Capricorn Highway at Emerald begins to rise approximately 2 hours after the start of the formation of the breach at the dam and peaks approximately 5½ hours later. For the PMF Flood with dam failure, the water level at the same location begins to rise 8 hours into the storm event and peaks approximately 9 hours after the start of the formation of the breach at the dam which occurs 6 days 17 hours into the storm event. For the failure cases it is unlikely that there would be sufficient warning time to evacuate the population at risk.
- For the Sunny Day and PMF failure cases the flood wave attenuates as it progresses downstream. In contrast, the PMF no failure flood shows an increase in peak flows resulting from the contribution of downstream tributary flows.
- Fairbairn Dam can safely pass a PMF event without overtopping.

SECTION 10



DEFINITIONS & ANALYSIS

- Incident, Emergency Response, Crisis and Business Continuity Management Manual
- Flood Event Definitions and Abbreviations
- Earthquake Assessment (Modified Mercalli Scale)
- Queensland Disaster Management System
- Weather Information (Flood Warning)



INCIDENT, EMERGENCY RESPONSE, CRISIS AND BUSINESS CONTINUITY MANAGEMENT MANUAL

PURPOSE

The purpose of the Manual is to provide a description of the framework that SunWater applies in managing various levels of incidents, from locally managed incidents through to emergency, crisis and business continuity management. It includes:

- definitions for the terminology used in incident management
- a description of the documentation for the different levels of an Incident / Emergency / Crisis
- a roadmap of the different levels of incident within SunWater and how they are to be managed, including a description of the escalation process when an Emergency worsens to become a Crisis
- a description of the phases of management of the different levels of incident, and how these may interrelate.

The Incident/Near Miss Management Plan (IMP), Emergency Management Plan (EMP), Crisis Management Plan (CMP) and Business Continuity Plan (BCP) must be read in conjunction with the Manual.



FLOOD EVENT DEFINITIONS AND ABBREVIATIONS

DEFINITIONS

• "DCF" or

"Dam Crest Flood" (Formerly IFF or Impending Failure Flood)

The flood Event which when routed through the Reservoir just threatens failure of the Dam.

The Reservoir is assumed to be initially at Full Storage Level

• "PMF" or

"Probable Maximum Flood"

The flood resulting from the Probable Maximum Precipitation, coupled with the worst flood producing catchments conditions that can be realistically expected in the prevailing meteorological conditions

• "PMP" or

"Probable Maximum Precipitation"

The theoretical greatest depth of precipitation for a given duration that is physically possible over a particular drainage system.

"SUNNY DAY FAILURE"

Unexpected failure of a dam not associated with flooding or natural disaster.

State of Emergency

As defined by the State Emergency and Rescue Management Act (1989)

OR As defined by the Dams Safety Act (1978)

ABBREVIATIONS

ANCOLD

Australian National Committee on Large Dams
DEMO

District Emergency Management Officer
District Emergency Operations Controller

DFL Design Flood Level

Department of Land and Water Conservation, NSW

DSU Dam Safety Unit, Department of Land & Water Conservation, NSW

FSL Full Supply Level

LEOCON Local Emergency Operations Controller
MDBC Murray Darling Basin Commission

MLD Megalitres per Day

MRMW Manager, River Murray Works
OIC Officer-In-Charge, Hume Dam
SES State Emergency Service
UHF Ultra High Frequency
VHF Very High Frequency

EL Elevation Level

AEP Annual Exceedence Probability

DCL Dam Crest Level



EARTHQUAKE ASSESSMENT (MODIFIED MERCALLI SCALE)

Not felt by humans, except in especially favourable circumstances, but birds and animals may be disturbed. Reported mainly from the upper floors of buildings more than 10 storeys high.

Dizziness or nausea may be experienced.

Branches of trees, chandeliers, doors and other suspended systems of long natural period may be seen to move slowly.

Water in ponds, lakes reservoirs, etc. may be set into wave oscillation of short to long durations.

MM 2 Felt by a few persons at rest indoors, especially by those on upper floors or otherwise favourably placed. The long-period effects listed under MM 1 may be more noticeable.

MM 3 Felt indoors, but not identified as an earthquake by everyone.

Vibration may be likened to passing of light traffic.

It may be possible to estimate the duration, but not the direction.

Hanging objects may swing slightly.

Standing motorcars may rock slightly.

MM 4 Generally noticed indoors, but not outside.

Very light sleepers may be wakened.

Vibration may be likened to the passing of heavy traffic, or to the jolt of a heavy object falling or striking the building.

Walls and frame of buildings are heard to creak.

Doors and windows rattle.

Glassware and crockery rattles.

Liquids in open vessels may be slightly disturbed.

Standing motorcars may rock, and the shock can be felt by their occupants.

MM 5 Generally felt outside, and by almost everyone indoors.

Most sleepers awakened. A few people frightened.

Direction of motion can be estimated.

Small unstable objects are displaced or upset.

Some glassware and crockery may be broken. Some windows cracked.

A few earthenware toilet fixtures cracked.

Hanging pictures move. Doors and shutters swing.

Pendulum clocks stop, start, or change rate.

MM 6 Felt by all.

People and animals alarmed.

Many run outside.

Difficulty experienced in walking steadily.

Some plaster cracks or falls. Isolated cases of chimney damage.

Windows, glassware, and crockery broken.

Objects fall from shelves, and pictures from walls.

Heavy furniture moved. Unstable furniture overturned.

Small church and school bells ring.

Trees and bushes shake, or are heard to rustle.

Loose material may dislodge from existing slips, talus slopes, or shingle slides.



MM 7 General alarm.

Difficulty experienced in standing.

Noticed by drivers of motorcars.

Trees and bushes strongly shaken. Large bells ring.

A few instances of damage to masonry.

Loose brickwork and tiles dislodged.

Un-braced parapets and architectural ornaments may fall.

Stone walls cracked. Weak chimneys broken, usually at the roof-line.

Domestic water tanks burst.

Concrete irrigation ditches damaged.

Waves seen on ponds and lakes.

Water made turbid by stirred-up mud.

Small slips, and caving-in of sand and gravel banks.

MM 8 Alarm may approach panic.

Steering of motorcars affected.

Masonry damaged, with partial collapse.

Chimneys, factory stacks, monuments, towers, and elevated tanks twisted or brought down.

Panel walls thrown out of frame structures.

Some brick veneers damaged.

Decayed wooden piles broken.

Frame houses not secured to the foundation may move.

Cracks appear on steep slopes and in wet ground.

Landslips in roadside cuttings and unsupported excavations.

Some branches may be broken off.

Changes in the flow or temperature of springs and wells may occur.

Small earthquake fountains.

MM 9 General Panic.

Masonry heavily damaged, sometimes collapsing completely.

Frame structures racked and distorted.

Damage to foundations general.

Frame houses not secured to the foundations shifted off.

Brick veneers fall and expose frames.

Cracking of the ground conspicuous.

Minor damage to paths and roadways.

Sand and mud ejected in alleviated areas, with the formation of earthquake fountains and sand craters.

Underground pipes broken.

Serious damage to reservoirs.

MM 10 Most masonry structures destroyed, together with their foundations.

Some well built wooden buildings and bridges seriously damaged.

Dams, dykes and embankments seriously damaged.

Railway lines slightly bent.

Concrete and asphalt roads and pavements badly cracked or thrown into waves.

Large landslides on river banks and steep coasts.

Sand and mud on beaches and flat land moved horizontally.

Large and spectacular sand and mud fountains.

Water from rivers, lakes, and canals thrown up on the banks.

Earthquake Effects

Earthquake Intensity

The effects of earthquake waves at a particular point is assigned using an intensity scale. This is an rbitrary scale based on observations of phenomena such as:

- the type and extent of damage,
- whether sleeping people were woken,
- whether items fell from shelves,
- whether the event was felt or heard.

The most common intensity scale used in Australia is the 12-point Modified Mercalli (MMI) scale. On this scale, intensities up to 5 are felt but cause no damage, while intensities from 6 to 12 cause increasing amounts of damage.

0011	ried Mercalli Intensity (MMI) Scale			
1	Not felt. Recorded by seismographs.			
2	Rarely felt, usually only on top floors of high buildings			
3	Felt indoors, like a passing light truck.			
4	Windows, dishes, doors rattle. Like passing train.			
5	Felt by all. Small objects upset.			
6	Books off shelves. Trees shake. Isolated damage.			
7	Difficult to stand. Many poor buildings damaged.			
8	Significant damage. Branches broken from trees.			
9	General panic. Serious damage. Ground cracking.			
10	Most buildings destroyed. Rails bent slightly.			
11	Rails bent greatly. Pipelines destroyed.			
12	Near total damage. Objects thrown into the air.			

Other intensity scales have been defined; the RF (Rossi-Forel) scale was introduced in the late 19th century, the JMA (Japan Meteorological Agency) scale is used in Japan and Taiwan; and the MSK and the more recent EMS (European Macroseismic Scale) are used in Europe. Most of these scales have twelve degrees of intensity which can be roughly (but not exactly) correlated between scales.

While all intensity scales are semi-qualitative they can be most useful for assessing historic earthquakes for which no seismic records exist.

Intensity Variability

An earthquake has a single magnitude, but intensity varies with distance. Maximum intensity normally occurs near the earthquake epicentre, with intensity values generally decreasing with distance.

Many factors affect surface ground motion, including topography and near-surface geology, especially soft surface sediments. These variations can be considerable, even over short distances. It is common to find intensities ranging by ± 1 unit in a neighbourhood, and not unusual to find values ± 2 or more.

Earthquake Size

The Size of Earthquakes

Earthquakes vary enormously in the amount of energy released, over a range exceeding a million million. It is not possible to measure the energy release directly, so it must be computed from measurements of the amplitude of the ground vibrations.

Earthquake Magnitude

The best known method of describing the size of an earthquake is the Richter magnitude scale, ML. This takes the logarithm of the ground displacement as measured by a seismograph, and applies a correction to account for the distance from the earthquake to the seismograph.

The logarithmic nature of the scale means that for each unit of magnitude there is a ten-fold increase in ground displacement. This equates to an approximately thirty-fold increase in energy release for each unit increase in magnitude.

An ML 1 or 2 earthquake releases a similar amount of seismic energy as a typical quarry blast. An ML 5 earthquake releases about the same seismic energy as a 10,000 tonne equivalent nuclear blast, such as that used at Hiroshima.

The Richter magnitude scale is not the only way to measure earthquake size (in the same way as "wattage" is not the only way to measure the size of a light bulb) and a range of different magnitude scales have been defined (eg. MS, Mw, Mb, md). Each scale is defined to be consistent with other scales but exact consistency is not possible as each scale measures a different aspect of the earthquake energy spectrum. Magnitudes values can range from less than 0.0 to over 9.0.

Fault Dimensions

The area of a fault that ruptures in a particular earthquake correlates with the magnitude of the earthquake as do the rupture duration and rupture displacement. Typical values for these parameters are shown in the following table. Note that these are averages only and values for individual earthquakes may vary considerably.

Hagnitude Hw	Fault area (km²)	Dimensions (km x km)	Duration (s)	Displacement (m)
4	1	1x1	0.3	0.05
5	10	3 x 3	0.5	0.15
6	100	10 x 10	1.5	0.5
7	1000	30 x 30	5	1.5
8	10,000	50 x 200	30	10

Copyright © 1997, 1998, Selsmology Research Centre (www.seis.com.au)

QUEENSLAND DISASTER MANAGEMENT SYSTEM

The Queensland Disaster Management System operates on three distinct levels. These are:

- Local Government
- Disaster District
- State Government

A fourth level, The Commonwealth, is also included in our Disaster Management System recognising that Queensland may need to seek Commonwealth support in times of disaster.

Each of these levels within the Queensland Disaster Management System has as its basis a committee structure supported by a disaster coordination centre. These committees and coordination centres are activated when required to manage and coordinate support for disaster stricken communities. When not activated, these committees meet to prepare for and practice their role within the Disaster Management System.

Figure 1 depicts the Queensland Disaster Management System including the link to the Commonwealth for National-level support when required.




Figure 1 - The Queensland Disaster Management System

Description of the System

The Queensland Disaster Management System has three principal tiers that quickly provide both technical and tangible assistance to disaster stricken communities.

Management of a disaster at the community level is conducted by Local Government who are responsible for the implementation of their Local Disaster Management Plan. If Local Governments require additional resources to manage the event, they are able to request support from their Disaster District Coordinator. This allows for the rapid mobilisation of resources at a regional or district level. If Disaster Districts resources are inadequate or inappropriate, requests for assistance can be passed to State via the State Disaster Coordination Centre. Finally, when State resources are inadequate or inappropriate, support from the Commonwealth can be obtained via <u>Emergency Management Australia</u> (EMA).

Reference: http://www.disaster.qld.gov.au/about/

A brief summary of each of the key components of the Queensland Disaster Management System is set out below:

- Local Disaster Management Group. (Formerly called Local Government Counter Disaster Committee). Local Disaster Management Groups (local groups) coordinate the response to a disaster at a local level. The Committees are usually chaired by the Mayor and the Local Government Chief Executive Officer is usually the Executive Officer of the committee. Local Government Counter Disaster Committees develop and maintain Counter Disaster Plans for their Shire. These Local Government Committees are best placed to decide what resources are needed, when they are needed and how best to apply such resources so as to minimise hardship and suffering. They play a key role in the Queensland Disaster Management System.
- District Disaster Management Group (formerly called Disaster District Control Group). There are 23 Disaster Districts in Queensland which are based on the Police Districts. The senior Police Officer in each district is designated as the Disaster District Coordinator who Chairs a Disaster District Control Group. These Disaster District Control Groups comprise representatives from regionally-based Queensland Government departments who are able to provide and coordinate whole-of-government support to disaster stricken communities. The Disaster Districts perform a 'middle' management function within the Disaster Management System by providing coordinated State Government support when requested by Local Governments.
- The State Disaster Coordination Group (SDCG) is the working body of the State Disaster Management Group (State Group) at State-level. SDCG members are designated liaison officers from each of the Departments represented on the State Group. This Group is the primary mechanism through which coordinated whole-of-government State-level support is provided to disaster-stricken communities.
- The State Disaster Management Group. The State Disaster Management Group (State Group) is established as the principal organisation under the new Act for the purposes of disaster management throughout the State. It replaces the State Counter-Disaster Organisation and its executive, the Central Control Group. In particular, the State Group is responsible for disaster mitigation and disaster planning and preparation at a State level and for coordinating whole-of-Government response and recovery operations prior to, during and after a disaster impact. This includes accessing interstate and/or Commonwealth assistance when local and State resources are exhausted or not available.

The State Group comprises Chief Executive Officers (CEO's) from all Queensland Government Departments. The CEO of the Department of the Premier and Cabinet is the Chair, while the Executive Director of Counter Disaster and Rescue Services is the Executive Officer.

- Major Incidents Group (MIG). The Queensland Government has established a MIG to provide high level Ministerial guidance and support in the event of a significant incident with major community consequences. Conceptually, membership of the MIG would be determined on an incident-by-incident basis and may include, but not be limited to:
 - Premier (Chair)
 - Treasurer
 - Attorney-General
 - · Minister for Police
 - · Minister for Emergency Services
 - Minister for Health

Reference: http://www.disaster.qld.gov.au/about/

WEATHER INFORMATION (FLOOD WARNING)

Using the Internet http://www.bom.gov.au/

