



From: John Tibaldi
Sent: Saturday, 15 January 2011 6:34 PM
To: Rob Drury
Subject: Full Document - JT Draft -.02
Attachments: Full Document - JT Draft - 02.docx
Updated effort.

QFCI

Date: 7/2/12 JM

Exhibit Number: 1095

INTRODUCTION

Wivenhoe Dam was constructed by the Queensland Government between 1977 and 1984. The dam is a 56 metre high, 2.3 kilometre long earth and rock embankment separated into two parts by a concrete gravity spillway. The spillway is controlled by 5 radial gates, each 12.0 metres wide by 16.0 metres high. Two saddle dam embankments are located on the left side of the reservoir.

The dam spillway capacity was upgraded in 2005. This was done primarily through the construction of a 164 metre wide secondary spillway through the right abutment of the existing dam. This spillway contains three eroding earth fill fuse plug embankments that are initiated at different dam levels in excess of EL 75.5.

The dam has two main functions by providing:

- A 1,165,000 ML storage at full supply level (FSL EL 67.0) providing an urban water supply for Brisbane and surrounding areas;
- Flood mitigation in the Brisbane River by providing a dedicated flood storage volume of 1,450,000 ML up to EL77 (this flood storage volume was increased to EL80m in 2005 changing the flood storage volume to 2,000,000 ML).

The dam has an EXTREME hazard classification under ANCOLD guidelines because of the significant development downstream in the Brisbane and Ipswich metropolitan areas, with the population at risk in the event of a dam failure numbering in the hundreds of thousands.

In accordance with the Queensland Regulatory program for dam spillway upgrades, a further upgrade of Wivenhoe Dam is scheduled to occur prior to 2035 to enable the dam to safely pass the Probable Maximum Flood. This work will involve the reconstruction of Saddle Dam 2 as a fuse plug spillway.

Wivenhoe Dam is currently excellent condition. Comprehensive Dam Safety reviews undertaken in accordance with ANCOLD guidelines have been undertaken in 1997 (Gutteridge, Haskins & Davey Pty Ltd), 2003 (Wivenhoe Alliance), 2006 (NSW Department of Commerce), 2009 (GHD) and September 2010 (Seqwater). The reports concluded that the design of the dam is in accordance with modern day standards and that there are no significant outstanding design or construction issues that require investigation.

WIVENHOE DAM FLOOD MITIGATION AND FLOOD OPERATIONS

Flood Mitigation

The Brisbane River catchment covers an area of approximately 14,000 square kilometres of which about half is below Wivenhoe Dam. Maximum overall flood mitigation effect is achieved by operating Wivenhoe Dam in conjunction with Somerset Dam. Although Somerset and Wivenhoe Dam reduce flooding in Brisbane City, major flooding can still occur. The Lockyer-Laidley Valley drains into the Brisbane River through Lockyer Creek that enters the Brisbane River just downstream of Wivenhoe Dam near Lowood. Another major tributary, the Bremer River, flows into the Brisbane River at Moggill. Wivenhoe dam has no control over inflows into the Brisbane River from both these major tributaries.

Wivenhoe Dam mitigates downstream flooding by storing incoming flood water during a rainfall event and releasing these waters at a reduced flow rate downstream to reduce flood impacts. The timing of the releases is also manipulated so that the aim is for outflows from the dam to impact on downstream areas only after the peak inflows from the Brisbane River's major tributaries have passed. However this aim cannot always be achieved in practice. This is because some large floods, such as the one currently being experienced, have the potential to overflow the dam's flood storage compartment. Should this occur, the dam would fail and the resulting damage and loss of life would be several orders of magnitude above that currently being experienced.

Therefore the basis of all flood operation decision making is to ensure the dam never fails. This is the reason that the dam's flood storage compartment would never be intentionally fully filled as additional inflows after this point would result in a dam failure.

Flood Operations

A real time flood monitoring and forecasting system has been established in the Wivenhoe and Somerset dam catchments. This system employs radio telemetry to collect, transmit and receive rainfall and stream flow information. The system consists of around 230 field stations that automatically record rainfall and/or river heights at selected locations in the dam catchments. Most of these field stations are owned by Seqwater with the remainder belonging to other agencies.

The rainfall and river height data is transmitted to Seqwater's Flood Operations Centre in real time. Once received in the Flood Operations Centre, the data is processed using a Real Time Flood Model (RTFM) to estimate likely dam inflows and evaluate a range of possible inflow scenarios based on forecast and potential rainfall in the dam catchments. The RTFM is a suite of hydrologic and hydraulic computer programs that utilise the real time data to assist in the operation of the dams during flood events.

Seqwater engineers use the RTFM for flood monitoring and forecasting during flood events to operate the dams in accordance with a Manual of Flood Mitigation (the origin of and objectives and procedures contained in the Manual of Flood Mitigation are explained in the following section of this document). Releases of water from the dams are optimised to minimise the impacts of flooding in accordance with the objectives and procedures contained in a Manual of Flood Mitigation.

MANUAL OF FLOOD MITIGATION FOR WIVENHOE AND SOMERSET DAMS

The original Manual of Flood Mitigation for Wivenhoe and Somerset dams was developed in 1992 during an extensive hydrological study of the Brisbane and Pine Rivers catchments by DPI, Water Resources that was reviewed by an external expert panel. Subsequently, the Manual was extensively reviewed during the Brisbane Valley Flood Damages Minimisation Study in 2006, with the latest comprehensive review of the Manual undertaken in 2009. Both of these reviews have included expert review panels comprising key stakeholders.

The Manual of Flood Mitigation is prepared by Seqwater as the owner of the dam and approved and gazetted by the Chief Executive of DERM in accordance with the Water Supply Act 2008. The manual defines flood objectives procedures; roles and responsibilities; and staffing and operational requirements for flood events impacting on Wivenhoe and Somerset dams.

The primary objectives of the procedures contained in the flood manual are, in order of importance:

- Ensure the structural safety of the dams;
- Provide optimum protection of urbanised areas from inundation;

- Minimise disruption to rural life in the valleys of the Brisbane and Stanley Rivers primarily, this involves minimising inundation of the six bridges below the dam upstream of Moggil);
- Retain the storage at Full Supply Level at the conclusion of the Flood Event.
- Minimise impacts to riparian flora and fauna during the drain down phase of the Flood Event.

During an event, the operation of the dam transitions between the following four operating strategies depending of the circumstances at the time. These procedures associated with these strategies are explained in detail in the Manual.

- **Strategy W1** – Primary consideration is given to Minimising Disruption to Downstream Rural Life. Under this strategy, the predicted water level is below 68.50 m AHD and the maximum release is 1,900m³/s.
- **Strategy W2** – Transition Phase moving from Minimising Disruption to Protecting Downstream Urban Areas. Under this strategy, the water level is predicted to be between 68.5 and 74.0 m AHD and the maximum release is less than 3,500m³/s.
- **Strategy W3** – Primary consideration is to Protect of Urban Areas from Inundation. Under this strategy, the water level is predicted to be between 68.5 and 74.0 m AHD but the maximum release is less than 4,000m³/s.
- **Strategy W4** – Primary consideration is to Protection the Dam. Under this strategy, the water level is predicted to exceed 74.0 m AHD and there is no limit to the maximum release. Consideration is given to managing flood releases to avoid fuse plug initiation if at all possible as this would compromise flood mitigation capacity in the short to medium term.

In addition to these strategies, historical records show that there is a significant probability of two or more flood producing storms occurring in the Brisbane River system within a short time of each other. Accordingly for each flood event, the aim is always to empty stored floodwaters within seven days after the flood peak has passed through the dams.